

CITY OF EVERETT FISH AND WILDLIFE HABITAT CONSERVATION AREAS (FWHCA) ASSESSMENT

HAT ISLAND SUBMARINE POWER CABLE REPLACEMENT PROJECT

OCTOBER 23, 2024



JEN-JAY, INC.

P.O. BOX 278, DEER HARBOR, WA 98243

EMAIL: INFO@JENJAYINC.COM

HAT ISLAND SUBMARINE POWER CABLE REPLACEMENT PROJECT

OCTOBER 23, 2024

Prepared for:

Snohomish County Public Utility District No. 1

c/o Jessica Spahr, Program Manager

P.O. Box 1107

Everett, WA 98206

United States of America

Prepared by:

Jen-Jay, Inc.

P.O. Box 278

Deer Harbor, WA 98243-0278

United States of America

This document should be cited as:

Jen-Jay, Inc. 2024. City of Everett Fish and Wildlife Habitat Conservation Area (FWHCA) Assessment. Hat Island Submarine Power Cable Replacement Project. October 23, 2024. Prepared Snohomish County Public Utility District No. 1; c/o Jessica Spahr, Program Manager.



Table of Contents

Table of Contents.....	3
List of Tables	5
List of Figures	5
List of Appendices.....	5
Abbreviations.....	5
1. General Information	7
1.1. No Net Loss Determination	8
2. Project Description	10
2.1. Project Site Description	11
2.1.1. Parcel Description.....	11
2.1.2. Vegetation Habitats.....	12
2.1.3. Presence of Forage Fish and Shellfish Beds	13
2.1.4. Flood Plain	13
2.1.5. Coastal Landform Characteristics	14
2.1.6. Inland Water	14
2.1.7. Geologically Hazardous Areas.....	15
2.1.8. Presence of Species of Concern	15
2.2. Construction Techniques and Sequencing.....	16
2.2.1. Pre-fabrication	17
2.2.2. Site Preparation	17
2.2.3. Construction Access.....	17
2.2.4. On-site Construction.....	17
2.2.5. Equipment Used	17
2.2.6. Materials Used.....	18
2.2.7. Work Corridor	18
2.2.8. Staging Area and Equipment Washouts	18
2.2.9. Stockpiling Areas	18
2.2.10. Running of Equipment During Construction.....	18
2.2.11. Clean-Up and Re-vegetation	18



- 2.2.12. Project Timing and Work Window 18
- 2.2.13. Duration of Construction..... 19
- 3. Critical Areas and Species Impact Assessment 19
 - 3.1. Critical Areas 19
 - 3.1.1. Coastal Vegetation 20
 - 3.1.2. Forage Fish and Shellfish Areas..... 21
 - 3.1.3. Inland Water Bodies 22
 - 3.1.4. Terrestrial Habitats 23
 - 3.2. Species of Concern..... 23
 - 3.2.1. Salmonids..... 24
 - 3.2.2. Rockfish..... 25
 - 3.2.3. Marine Mammals 26
 - 3.2.4. Dungeness Crab 28
- 4. Cumulative Impacts Assessment..... 29
 - 4.1. Direct Impacts..... 29
- 5. Mitigation Procedures for Critical Areas..... 29
 - 5.1. Conservation Measures..... 29
 - 5.2. Avoid Impacts 30
 - 5.3. Minimize Impacts 30
 - 5.4. Mitigate Impacts..... 31
 - 5.5. Reduce or Eliminate Impacts Over Time..... 31
- 6. Conclusion 31
- 7. References 32
- 8. Jen-Jay, Inc. Qualifications 38



List of Tables

Table 1. Critical areas and buffers within 300 feet of project activities, page 20.

Table 2. Species of Local Concern that may be affected by project activities, page 23-24.

Table 3. Southern Resident Killer Whale sightings during the proposed work window, page 27.

List of Figures

Figure 1. Port of Everett property aerial image and site photos, page 9.

Figure 2: WDFW Forage Fish Spawning Map, page 13.

Figure 3: WDOE Coastal Atlas Coastal Landforms, page 14.

List of Appendices

Appendix 1. Hat Island to Port of Everett Cable Crossing Plan and Profile (Snohomish Public Utility District No. 1)

Appendix 2. Preliminary Eelgrass and Macroalgae Habitat Survey (Jen-Jay, Inc.)

Appendix 3. Geotechnical Report (Haley & Aldrich, Inc.)

Appendix 4. Hat Island Multibeam Bathymetric Survey Report (Tetra Tech, Inc.)

Abbreviations

BMPs	Best Management Practices
DPS	Distinct Population Segment
EMC	Everett Municipal Code
ESA	Endangered Species Act
ESU	Evolutionarily Significant Unit
FEMA	Federal Emergency Management Agency
FF	Forage Fish
FR	Federal Register
FWHCA	Fish and Wildlife Habitat Conservation Area
HAT	Highest Astronomical Tide



HDD	Horizontal Directional Drilling
LUCAAR	Land Use, Critical Area and Archaeology Review
MLLW	Mean Lower Low Water
MMPA	Marine Mammal Protection Act
NFIP	National Flood Insurance Program
NMFS	National Marine Fisheries Service
NNL	No Net Loss
NOAA	National Oceanic and Atmospheric Administration
NMFS	National Marine Fisheries Service
OHWM	Ordinary High-Water Mark
PHS	Priority Habitat Species
SAV	Submerged Aquatic Vegetation
SC	Snohomish County
SCC	Snohomish County Code
SnoPUD	Snohomish County Public Utilities District No. 1
SRKW	Southern Resident Killer Whale
TPN	Tax Parcel Number
TPZ	Tree Protection Zone
USACE	U. S. Army Corps of Engineers
USDA	U. S. Department of Agriculture
USGS	U. S. Geological Service
WAC	Washington Administrative Code
WDFW	Washington Department of Fish and Wildlife
WDNR	Washington Department of Natural Resources
WDOE	Washington Department of Ecology
WNHP	Washington Natural Heritage Program



1. General Information

Applicant: Snohomish County Public Utility District, No. 1
P.O. Box 1107
Everett, WA 98206

Contact: Kim Middleton, Jen-Jay Inc.

Office Phone: (360) 376-4664

Email: kim@jenjayinc.com

Physical locations of proposed work:

Port of Everett Property

P.O. Box 538

Everett, WA 98206

Tax Property Number: 29042500400200

Section 25, Township 29, Range 04

Lat/Long: 47.97122° N; 122.22999° W

Water body: *Port Gardner Bay, Possession Sound*



1.1. No Net Loss Determination

Everett Municipal Code 19.37.076 states “An applicant must submit a critical area study by a qualified professional that documents that the proposed development design/standards will result in a net improvement of the functions of the critical area over that which would be obtained by applying the standard prescriptive measures contained in this chapter. The study must address the best available science as it relates to the critical area functions.”

No net loss determinations are made by a qualified biologist. Snohomish Public Utility District No. 1 produced the project drawings dated March 17, 2023 (**Appendix 1**). Jen-Jay, Inc. performed both a Preliminary Eelgrass Macroalgae Habitat Survey and site visit on June 11, 2023 (**Appendix 2**). Haley & Aldrich, Inc. created a Geotechnical Report September 1, 2023 (**Appendix 3**). Tetra Tech, Inc. performed all necessary bathymetry to accurately locate appropriate placement of the proposed replacement submarine cable between Hat Island and the Port of Everett (**Appendix 4**). A vicinity map and site photos are included in **Figure 1**.



Port of Everett-Hat Island Submarine Power Cable Replacement Project

Photo Page



Jen-Jay, Inc.

Figure 1. Aerial image showing Port of Everett property and proposed project site with location of HDD ingress and egress. Site photos include (A) Pigeon Creek Beach to the south of the project site; (B) HDD site immediately located inside the chain link fence of the Port of Everett project site; and (C) aerial view of the project site at low tide showing the beach contours.



2. Project Description

The project is the replacement and rerouting of a submarine power cable between the Port of Everett and Hat (Gedney) Island. Jen-Jay, Inc. has been hired by Snohomish County Public Utility District No. 1 (SnoPUD) to evaluate critical areas and ecological functions and values present in the vicinity of the proposed replacement submarine power cable that serves Hat Island. This study is to fulfill all the requirements of the critical areas report as described in Everett Municipal Code (EMC) 19.37.073.

Both proposed ends of the replacement submarine power cable are located within Snohomish County; however, the Port of Everett falls under the jurisdiction of the City of Everett. As such, a separate Fish and Wildlife Habitat Conservation Areas Assessment has been composed for Snohomish County to discuss the proposed submarine power cable replacement termination point on Hat Island.

This Wildlife Habitat Conservation Areas Assessment for the City of Everett specifically addresses the proposed Port of Everett site location immediately north of Pigeon Creek Beach inside the Port of Everett property, where the replacement submarine cable terminates in Everett, Washington under the City of Everett's jurisdiction.

Snohomish County Public Utility District No. 1 (SnoPUD) is the twelfth largest public utility in the United States and the second largest in Washington state. SnoPUD serves the 875,000 residents of Snohomish County and Camano Island at over 373,000 homes and businesses. SnoPUD also supplies water service to over 23,000 homes. The public utility's territory covers more than 2,200 square miles (SnoPUD 2024).

Hat (or Gedney) Island is a small, 436-acre, private island located west of Everett, WA, and in between Whidbey and Camano Islands in *Possession Sound*. The island is the permanent or vacation home to approximately 260 families. The island is serviced by a passenger ferry and bus, and houses several community beaches, a fire station, a yacht and golf club, a 9-hole golf course, and a 127-slip marina. The island is small and without stores so vehicles on island are used to transport people from the ferry to their respective homes (HICA 2024).

Snohomish PUD No. 1 provides electrical service to Hat Island via an existing, near-50-year-old submarine power distribution cable. This 12kV electrical distribution cable extends from Mission Beach, west of Marysville, WA, on the Tulalip Reservation, to Hat Island, covering a distance of approximately 16,000 feet. SnoPUD serves Hat Island from the Tulalip substation, circuit 12-507. The electric service also powers the island's drinking water system. The existing, three-phase cable was installed in 1974. It is nearing the end of its serviceable life and is at risk of failure, with only two of the three conductors currently functioning. The lost phase, which occurred mid channel, indicates that the waterproof function of the cable is compromised. The compromised cable could lose another phase at any time, and the power cable is the only source of power to Hat Island and its residents. The new cable installation is proposed in order to avoid a potential emergency situation which would isolate the residents of Hat Island from electric service.



The proposed project is the installation of a new, 3.8-inch three-phase electric submarine cable from the mainland within the Port of Everett to service Hat Island. To continue reliable service to district customers, the existing cable will remain energized while the new cable is installed.

The existing mainland cable termination point currently runs beneath an occupied residence. A new cable route is proposed to be located south of the existing cable to ensure protection of the existing cable during installation activities and to facilitate the Port of Everett landfall location near the northern *Pigeon Creek* shoreline on the mainland side.

The proposed 3.8-inch three-phase submarine cable with fiber optics will be directly laid on the seafloor. At the two landfall sites, the cable will be placed within a high-density polyethylene (HDPE) conduit that has been previously installed using horizontal directional drilling (HDD) and connected to the submarine cable termination vault. The proposed HDPE conduit will have an outer diameter of 10 inches and will be drilled to an approximate depth of 75 feet before daylighting on the seafloor at approximately -50' MLLW, which is approximately 1,000 linear feet waterward from the HDD entry point on the Port of Everett property (project drawings, Appendix 1). HDD techniques were determined to be the best option to prevent the submarine cable from interfering with other utility easements, vessel traffic and anchoring and to minimize disturbance of potentially chemically loaded sediment within the project area at the Port of Everett.

2.1. Project Site Description

The proposed submarine cable replacement project is located across *Possession Sound* and terminates in two locations: on the southwest end Port of Everett properties in Everett, WA, at TPN 29042500400200 and adjacent to the southern end of the Hat Island Marina on Hat Island Community Association, Inc. property at TPN 00466300003001 (SCOPI 2024). The shoreline description at the project location was determined using the Federal Emergency Management Agency (FEMA) Flood Hazard Zones (FEMA 2024); Washington Department of Fish and Wildlife (WDFW) Priority Habitat Lists (WDFW 2024 PHS); WDFW Forage Fish Spawning Maps (WDFW 2024 FF); Washington Department of Ecology (WDOE) Coastal Atlas (WDOE 2024 Atlas); Washington Department of Natural Resources (WDNR) Forest Practices Map (WDNR 2024 FPAMT); WDNR Natural Heritage Program (WNHP) (WDNR 2024 WNHP); WDNR Natural Hazards (WDNR 2024 Hazards); Snohomish County Assessor (SCOPI 2024); Map Everett (Map Everett 2024); as well as a Preliminary Eelgrass and Macroalgae Habitat Survey (Appendix 2) and a site visit, both conducted on June 11, 2023, by Jen-Jay, Inc.

2.1.1. Parcel Description

The City of Everett landfall parcel is outside of the metropolitan area and has a Comprehensive Plan designation of industrial and resource lands. The parcel has Shoreline Master Program designations of Urban Deep Water Port on the northern end of the upland portion of the parcel, Urban Conservancy at the southern upland end, and the tidelands are designated Aquatic Conservancy. The upland portion of the parcel ends at the terminus of Terminal Avenue and consists of a storage parking lot with vehicles, storage containers, and



industrial equipment for the Port of Everett, and is surrounded with chain link fencing. Southwest of the storage lot is a small park at Pigeon Creek Beach with a few trees and shrubs with beach access. The southeastern parcel boundary has electrical lines that will be used to tie the Hat Island cable into the electrical grid and railroad tracks run along the southeast side of the project parcel.

The proposed site at the Port of Everett is an equipment storage facility sitting on reclaimed and armored land next to a railroad track. Sawmill operations were held on the proposed project site parcel and the parcel to the northeast from the late 1800s to 1980s (Port of Everett 2018). Washington Department of Ecology (WDOE) documents five (5) Category 5-303d water chemical listings, twenty-one (21) Category 1 water chemical listings, and one (1) Category 2 sediment chemical listing in the proposed project parcel region. Due to the high chemical presence in the Port of Everett, HDD has been proposed to help minimize sedimentation perturbation within the nearshore environment during cable installation.

Much of the shoreline of the parcel is artificially armored with some natural shoreline. Shoreline ecological functions present at the proposed project site include attenuation of wave and tidal energy; recruitment of large woody debris and other organic matter; distribution of upland runoff and sediment movement; provision of habitat for native aquatic and shoreline-dependent fish and wildlife. The armoring reduces erosion and offers slope stability in the immediate area.

2.1.2. Vegetation Habitats

The Coastal Atlas indicates that there is no documented eelgrass (*Zostera marina*) nor kelp habitat at the project site. The nearest patchy fringe eelgrass habitat is documented over 650 feet southeast of the project site, beginning on the southern portion of Pigeon Creek Beach. The nearest patchy fringe kelp is documented over four miles northwest of the project site along the southern coast of Hat Island and across *Possession Sound*. A site visit and a Preliminary Eelgrass Macroalgae Habitat Survey were conducted by Jen-Jay, Inc. on June 11, 2023 (Appendix 2). Any submerged aquatic vegetation (SAV) pertinent to the Port of Everett landfall is detailed below as per each nearshore marine habitat region; however, no SAV habitat was detected at this project site.

- **Upland:** a gradually sloped beach made up of collected, large driftwood logs and rocks ranging from 6" to 48" in diameter; a few deciduous trees and shrubs, native and non-native grasses; and a chain link wire fence enclosed around an industrial storage yard pertinent to the Port of Everett's commercial needs. A biodiversity area and corridor exist on the upland side of the railroad tracks and is southeast of the project site.
- **Upper Shore Zone (+5' MLLW to HAT):** substrate is sandy mud with 0" to 12" rock and is devoid of vegetation.
- **Lower Shore Zone (-10' MLLW to +5' MLLW):** substrate is sandy mud devoid of any vegetation.



- **Deep Shore Zone (deeper than -10' MLLW):** substrate is sandy mud devoid of any vegetation.

Eelgrass habitats will be discussed further in the Critical Areas section 3.1.1 Coastal Vegetation.

2.1.3. Presence of Forage Fish and Shellfish Beds

No shellfish areas of concern have been documented in the vicinity of the project and no forage fish are documented on the shoreline of the project site (Figure 2). The nearest Pacific sand lance and surf smelt spawning habitats are approximately a half mile southwest of the project site along Darrington Beach. The nearest herring spawning area is approximately 6.5 miles northwest of the project site in *Tulalip Bay*. Forage fish and shellfish areas of concern will be discussed further in the Critical Areas Section 3.1.2 Forage Fish and Shellfish Areas.




Figure 2: WDFW Forage Fish Spawning Map showing Pacific sand lance and surf smelt spawn along the beach southwest of the project site.

2.1.4. Flood Plain

The shoreline at the project site is located within an Area of Special Flood Hazard with base flood elevation of +16' MLLW. The flood hazard area is zoned “VE”, which indicates that there is a 1% annual chance of being flooded with fast-moving or storm-induced waves of three feet or higher in addition to the base flood elevation. The City of Everett database designates the VE Zone as a high-risk coastal area as per flood hazard assessments.



The HDD project site is approximately +25' MLLW and is not anticipated to be affected by flood inundation during drilling. The cable will be in the HDD drilled conduit or lying on the seafloor and will be protected from flooding.

2.1.5. Coastal Landform Characteristics

The Coastal Atlas documents the shoreline slope stability as modified at the Port of Everett parcel. An approximate 225-foot stretch of coastline along Pigeon Creek Beach is designated as an accretion shoreform within the parcel’s boundaries. The remainder of the northern coastline and an approximately 175 feet of coastline to the south of the accretion shoreform is designated as a transport zone. The remaining 375 feet of coastline at the most southwestern portion of the project’s parcel is designated as feeder bluff (Figure 3). Littoral drift along this stretch of coast is from southwest to northeast.




Figure 3: DOE Coastal Atlas showing the various coastal landforms at the project site.

2.1.6. Inland Water

Freshwater is found in the atmosphere, on the Earth’s surface, and underground. Surface freshwater ecosystems consist of rivers, streams, lakes, reservoirs, ponds, and wetlands (USGS 2018). These ecosystems are crucial for life and provide drinking water, water for agriculture, energy production, habitats for aquatic life, recreational opportunities, water purification and storm and flood relief. Freshwater is considered a renewable resource.

Washington DNR Forest Practices Map documents three streams within 300 ft of the project parcel at the Port of Everett. Two non-fish drainage streams are unnamed and the third is the fish bearing *Pigeon Creek No. 1* that empties onto Pigeon Creek Beach and is approximately 500 ft southwest of the project site.



The City of Everett’s map database does not document any wetland habitat near the Port of Everett project parcel. The wetland habitats nearest to the project parcel are documented by the City’s database along the banks of some of these freshwater streams. The most proximate wetland habitat to the project site according to the City of Everett database is over 2,000 feet east, or 0.4 mile away, from the landward Port of Everett cable access point at the upland source of an unnamed creek.

2.1.7. Geologically Hazardous Areas

The immediate shoreline at the project site is classified as Pleistocene continental glacial drift. The geotechnical report conducted by Haley and Aldrich (Appendix 3) describes the project site at the Port of Everett as having an approximately ten feet of fill layer of sand and gravel over the original beach soils composition.

The project site shoreline is documented on Coastal Atlas as modified and slopes upward to an approximate elevation of +25’ MLLW at the power cable landfall site at the Port of Everett storage lot. The entire marine coastline of Washington State is susceptible to tsunamis inundation. The areas bordering Puget Sound that are most prone to inundation flooding occur in lowland areas.

According to the City of Everett’s mapping database, the parcel has no documented landslide hazards; however, immediately adjacent to the project parcel and across the railroad tracks, the steep slopes are documented as a very high and severe landslide area. The entire project parcel has documented seismic hazards with moderate to high liquefaction susceptibility.

Haley & Aldrich, Inc. composed a soil conditions memorandum for subsurface traits at the proposed site of the submarine cable at both the Hat Island and the Port of Everett sites. The conclusions of these geotechnical observations are detailed in their report dated September 1, 2023 (Appendix 3).

2.1.8. Presence of Species of Concern

Some species of concern may occur at or near the project site. For waterfront property, some salmon and rockfish species have the potential to be present in the nearshore habitat of the project site. Salmon and rockfish will be discussed further in the Species of Concern Section 3.2.1 Salmonids and Section 3.2.2 Rockfish.

ESA listed marine mammals, such as humpback, gray, and Southern Resident Killer Whales (SRKW), may be found throughout the Salish Sea and Puget Sound regions. The project site is located within quadrat 386 with 128 SRKW sighting days documented from 1999-2022 within the work window for tidal reference area #7 of July 15th to February 15th. Due to the shallow and highly commercialized waters around the Port of Everett, there is a low probability of these whales occurring in the vicinity of the project site. Whales will be discussed further in the Species of Concern Section 3.2.3 Marine Mammals.



Dungeness crab, coho salmon, and resident coastal cutthroat all have the potential to be in the project area and will be discussed further in the Species of Concern Section 3.2.

2.2. Construction Techniques and Sequencing

The proposed submarine power cable installation between the Port of Everett and Hat Island will be conducted in compliance with all requirements set forth by county, state, and federal agencies. HDPE conduit will be installed using HDD at both landfalls to avoid sensitive habitats, potentially contaminated soils, and interference with other easements. The new submarine cable will be installed into the conduit from the waterward end and threaded through the conduit. The cable will be directly laid on the seafloor from reels on a construction barge and installed into the conduit on the other side. The cable will be connected to the submarine cable junction vault at each of the landfall project sites. Installation is expected to take place in two steps: HDPE conduit installation via HDD on both landfalls and cable installation via a construction barge from the Port of Everett to Hat Island. The following construction techniques and sequencing have been provided by the project managers at Snohomish Public Utility District No. 1, Jessica Spahr and Eric Schneider.

Horizontal Directional Drilling (HDD) is a trenchless pipeline installation technique during which a horizontal directional drill rig is used to install the pipeline beneath the substrate. An HDD pilot bore is advanced along a pre-determined alignment beneath the seabed to the exit point where the bore will emerge to the surface of the seafloor. Clean bentonite clay drilling fluid is used to help facilitate the drilling of the bore and keep the bore hole open during the multiple steps of the drilling operation. It is anticipated that small amounts of bentonite clay will disperse to the unvegetated seabed at the exit point.

To avoid disturbances of potentially contaminated substrate and other utilities above the HDD route, the bore will be located up to 75 feet below the surface of the seabed to prevent what is known as “frack-out.” Frack-out occurs when a shallow HDD operation forces excess drilling fluid (clay) upward through the interstitial spaces in the seafloor substrate, depositing clay in an undesired location. For sensitive SAV like eelgrass, the fine clay may cause shading.

At the completion of the borehole preparation, the conduit is connected to the pull-head for simultaneous installation as the drill rod and reamer are retracted from the borehole for the final time. The two ends of the conduit will be capped until the cable is ready to be installed.

The cable will be direct-laid along the unvegetated substrate in the deeper portions of *Possession Sound* from a barge-mounted spool using support vessels and divers. At the Port of Everett landfall site, the cable will be spooled out and floated on the surface. A diver and support vessels will position the cable end down to the waterward end of the HDD preinstalled conduit. A diver will assist the cable being fed through the conduit to the land-based termination vault where it will be connected to the existing infrastructure via overhead wires on poles. The method employed on the Port of Everett side of the cable route will be similar on the Hat Island



termination point. The total length of the submarine cable is approximately 30,000 feet from termination vault to termination vault.

2.2.1. Pre-fabrication

The new submarine power cable, HDPE conduct, power vault, and fiber splice vault will be prefabricated. Materials and equipment will be brought to the Port of Everett project site by trucks on road access and on a construction barge.

2.2.2. Site Preparation

Construction crew will examine the tidelands surrounding the project site to ensure a safe access corridor for the barge to reach all project components without risk of hull or substrate damage.

2.2.3. Construction Access

HDD construction equipment will access the landward project site from the existing Port of Everett storage lot road. Construction access to the waterward site to install the cable will be from a construction barge.

2.2.4. On-site Construction

Horizontal directional drilling (HDD) will be used to install a HDPE conduit to traverse the upland termination point with a predetermined offshore exit point (see Appendix 1). Best management practices (BMPs) will be implemented to prevent construction-related pollution from entering the nearshore or offshore habitats. These BMPs will include, but are not limited to, on-site materials (straw wattles, silt fencing, etc.) for erosion control and a frac-out contingency plan to prevent silt-laden water from entering the nearshore during HDD.

The submarine power cable will be fed into the preinstalled conduit and then laid directly on the seafloor using a construction barge. On the upland landfall site at the Port of Everett, the cable will exit the conduit and be connected to the newly installed power vault and fiber splice vault, then attached to the existing infrastructure via overhead power lines on poles.

2.2.5. Equipment Used

Trucks and work vehicles will be used to transport materials, tools, and personnel to the Port of Everett landward construction site lot. An excavator, drill rig, and associated equipment will be used during HDD and conduit installation. Whenever possible, hand tools will be used during construction to assemble new components for the submarine power cable terminal structure.

Barge stern-mounted spools of cable will be used to install the new submarine power cable. Power tools and hand tools will be used to connect the new cable from the HDD upland exit point to the existing infrastructure at the Port of Everett.



2.2.6. Materials Used

Approximately 30,000 feet of three-phase submarine cable and approximately 1500 feet 10-inch HDPE conduit.

2.2.7. Work Corridor

Vehicles, equipment, and personnel will operate along the paved access road and parking area at the cable access point on Port of Everett property, as well as on the water via the construction barge. Work will be limited to the locations where the landward HDD conduit installation is taking place and the marine regions covered by the construction barge to unroll the new submarine cable along the seabed. The work corridor will include areas wide enough for necessary equipment to access the sites.

2.2.8. Staging Area and Equipment Washouts

Staging for upland activities for the HDD will occur within the Port of Everett property immediately adjacent to the upland cable access point. When finished, all construction equipment will be loaded onto work trucks and transported to an approved, contained area for washouts. All waterward staging activities will occur on the construction barge. Equipment wash outs will not occur at the project location in the marine setting. Any necessary wash outs will occur at an approved facility.

2.2.9. Stockpiling Areas

The barge and upland cable termination areas will hold all construction materials during the project. All construction debris will be stored for later disposal at an approved upland facility upon completion of the project.

2.2.10. Running of Equipment During Construction

Equipment will be running off and on throughout the on-site construction phase. All equipment will be kept in good running order, free of leaks or debris, and will be running only when required.

2.2.11. Clean-Up and Re-vegetation

All barge-related construction debris will be stored on the barge for later disposal at an approved upland location. Upland construction areas will be cleaned of all construction debris. All construction equipment and debris will be removed to an approved upland facility for storage or disposal upon completion of the project. Disturbed soil will be returned to the existing condition prior to the commencement of project activities.

2.2.12. Project Timing and Work Window

All proposed construction and barge access will take place during WDFW and Army Corps of Engineers (ACOE) approved in-water work windows for the protection of fish in Tidal Reference Area 7. Due to the use of HDD to avoid sensitive habitats, the proposed work window for this project is July 15th – February 15th, at appropriate tides during daylight hours.



This work window is proposed to protect sensitive salmonid and forage fish species which may use the waters near the project area.

2.2.13. Duration of Construction

On-site construction timing is to be determined by the contractor, but it is anticipated to take no more than two weeks.

3. Critical Areas and Species Impact Assessment

The installation of an approximately 6-mile submarine power cable between the Port of Everett's access site and Hat Island's existing power vault has a variety of possible effects to critical areas and species within those regions.

The potential effects from the proposed project include the following:

1. Grounding the barge during cable installation.
2. Deleterious materials enter the water during construction.
3. Impacts to wildlife due to increased noise, particularly noise associated with horizontal directional drilling (HDD).
4. Impacts due to barge and HDD activities, such as oil discharge, drilling fluid, or other hazardous substances.
5. Temporary, increased turbidity in the water column due to horizontal directional drilling and cable installation.
6. Increased benthic hard substrate in the form of a submarine power cable.

Construction activities will be done in a manner that will minimize the overall potential effects on critical areas caused by the proposed actions. These activities will be conducted during approved work windows and appropriate hours and tides and with the implementation of best management practices laid out in WDOE Storm Water Management Manual for Western Washington Volume II (WDOE, 2024). to prevent potential negative effects to identified sensitive species and critical habitats located within 300 feet of the proposed development. Impacts will also be reduced by using appropriate construction design, techniques, and best management practices (BPMs), and are outlined in Section 5.1 Conservation Measures.

3.1. Critical Areas

Critical areas are important habitats for the protection of valuable ecosystems and the ecological services they provide. The critical areas and buffers that are located within 300 feet of the proposed project site and may be affected by project activities are identified in Table 1. Site data is based on information provided by the Federal Emergency Management Agency (FEMA) Flood



Hazard Zones (FEMA 2024); Washington Department of Fish and Wildlife (WDFW) Priority Habitat Lists (WDFW 2024 PHS); WDFW Forage Fish Spawning Maps (WDFW 2024 FF); Washington Department of Ecology (WDOE) Coastal Atlas (WDOE 2024 Atlas); Washington Department of Natural Resources (WDNR) Forest Practices Map (WDNR 2024 FPAMT); WDNR Natural Heritage Program (WNHP) (WDNR 2024 WNHP); WFDNR Natural Hazards (WDNR 2023 Hazards); Snohomish County Planning and Development Services (SC 2022 PDS Map Portal); Map Everett (Map Everett 2024); as well as a Preliminary Eelgrass Macroalgae Habitat Survey (Appendix 2) and site visit on June 11, 2023, by Jen-Jay, Inc.

Table 1: Critical areas and buffers that are located within 300 feet of the proposed project site and may be affected by project activities.

Critical Areas	Mapped at Site	Occurrence	Impact
Coastal Vegetation	None	Does not occur	NNL
Forage fish, shellfish	None	Does not occur	NNL
FEMA Flooded Areas	VE (EL +16')	Occurs	NNL
Coastal Landforms	None	Does not occur	NNL
Inland Water	Freshwater streams	Occurs	NNL
Terrestrial Habitats	Biodiversity Areas and Corridor: Snohomish County Park Lands	Occurs	NNL
Geologically Hazardous Areas	Tsunami; flood; seismic hazard	Occurs	NNL

EL = Elevation Level in feet MLLW; **NNL** = No-net loss

3.1.1. Coastal Vegetation

Sensitive and important submerged aquatic vegetation (SAV) is common in the nearshore environment of *Possession Sound*. Eelgrass and kelp are known to be valuable habitats for forage fish, as well as a nursery ground for numerous other valuable and protected fish species such as rockfish and salmon. Loss of eelgrass and kelp habitat can play a significant role in the degradation of the nearshore marine food web and lead to population declines in numerous sensitive species.



Submerged Aquatic Vegetation

No eelgrass or macroalgae were found during the Preliminary Eelgrass Macroalgae Habitat Survey (Appendix 2), although patchy fringe eelgrass (*Zostera marina*) has been documented overlapping with the project parcel but is over 650 feet southwest of the proposed cable access site. There is no documented kelp near the project site. The substrate offshore was documented as sandy mud with a presence of 0" to 12" rock.

Utilization of HDD techniques will avoid nearshore habitats by drilling under the substrate and daylighting approximately 1000 feet offshore at approximately -50' MLLW. This depth will guarantee the construction barge will avoid grounding out on any nearshore habitat. No long-term adverse impacts to submerged aquatic vegetation habitats are expected based on the project proposal. Construction activities are not anticipated to have any direct effect on eelgrass and kelp in the nearshore environment.

No net loss of eelgrass nor kelp habitat is anticipated.

3.1.2. Forage Fish and Shellfish Areas

Forage Fish Spawning and Holding Areas

In marine ecosystems, forage fish frequently serve as crucial trophic connectors, bridging the gap between zooplankton and the wide array of fish-eating species that populate the *Salish Sea* (Seldon and Baker 2023). Forage fishes are small schooling species that are prey for sea birds, marine mammals, and other fishes including Pacific salmonids. Surf smelt (*Hypomesus pretiosus*) ranges from *Prince William Sound*, Alaska to Long Beach, California, and spawns on many beaches in *Puget Sound*. Surf smelt spawn on beaches with a sand and gravel mix, with a grain size about 1-7 mm, at approximately +7' MLLW to the extreme high water (EHW). Pacific sand lance (*Ammodytes personatus*) is found from the Aleutian Islands of Alaska to Southern California and spawn on appropriate beaches scattered throughout *Puget Sound*. The Pacific sand lance spawning beach preference can overlap with surf smelt with a wider range between +5' MLLW to EHW. Pacific sand lance spawn on a beach composed of finer sand and gravel with most of the grain size ranging from 0.2-0.4 mm in diameter. The Pacific herring (*Clupea pallasii*) are a pelagic species found throughout the northern *Pacific Ocean*. Within *Puget Sound*, Pacific herring move into nearshore areas and congregate into specific holding areas before spawning. Pacific herring spawn in shallow waters by depositing their sticky eggs on submerged aquatic vegetation or rocky substrate mainly between late January to early April (Penttila 2007 and Froese and Pauly 2024). Adults and juveniles of forage fish species, including Pacific sand lance, surf smelt, and Pacific herring, are typically found occupying or transiting through nearshore habitat throughout northern *Puget Sound* (Allen and Smith 1988; Paul et al. 1997; Yang and Nelson 2000; Mecklenburg et al. 2002). Forage fish could forage, rest, or move within marine areas adjacent to the project site as this is a nearshore area within the *Puget Sound*.



Forage fish are not documented on the shoreline of the project site. The nearest sand lance and surf smelt spawning habitats are approximately a half-mile southwest of the project site along Darrington Beach. The nearest pre-spawner herring holding area is approximately 5.5 miles northwest of the project site in the inlet between Camano Island and mainland Washington. The nearest herring spawning area is approximately 6.5 miles northwest of the project site in *Tulalip Bay*.

The highly industrialized shoreline at the proposed project site is primarily sandy mud and lacks the ideal substrate at the shoreline that would serve as high value forage fish spawning habitat. For this reason, it is not expected that forage fish would use the parcel's shoreline for spawning. Construction activities are not anticipated to have any effect on forage fish spawning and holding areas in the nearshore environment, as none have been documented within the vicinity of the proposed project. Additionally, utilizing HDD methodology helps minimize any nearshore habitat effects from the submarine cable installation. Implementation of best management practices as listed in 5.1 Conservation Measures and minimum requirements for construction pollution prevention during landward conduit installation using HDD are expected to prevent stormwater runoff from entering the nearshore environment during construction. The proposed project activities are not expected to generate any long-term negative impacts to the nearshore if best management practices are implemented.

No net loss of forage fish or forage fish habitat is anticipated.

3.1.3. Inland Water Bodies

The waters of Washington State are defined in WAC 222-16-030 as Type S, F, Np, or Ns. Type S are waterbodies assigned as shorelines of the State. Type F are natural waterbodies, not designated as Type S, that are used by fish. Type Np are perennial, non-fish bearing water and Type Ns are non-fish bearing waters that exist seasonally. The seasonal, non-fish bearing habitat streams have surface flow that is not present for at least some portion of a year with normal rainfall and are not located downstream from any perennial stream.

Washington DNR maps three streams near the project parcel at the Port of Everett. Two are unnamed, non-fish bearing creeks and the other is the fish bearing *Pigeon Creek No. 1*. All streams empty onto Pigeon Creek Beach. Coho salmon and resident coastal Cutthroat mapped to occur in *Pigeon Creek* will be discussed further in 3.2.1 Salmonids.

Sound producing project elements are proposed and include HDD conduit installation methods. These sounds are anticipated to be non-injurious at close range but may result in minimal and temporary behavioral disturbance to individual fish present in the marine waters at Pigeon Creek Beach. There may be a temporary increase in turbidity at the time of construction during HDD daylighting and cable installation at approximately 1000 feet offshore from the project site. It is assumed the turbidity will disperse and clear within a few



tidal cycles. BMPs will be implemented for the in-water construction activities and no long-term impacts to the streams are anticipated. The proposed project is anticipated to avoid the nearshore habitats entirely through HDD installation techniques for the new cable.

No net loss of stream is anticipated.

3.1.4. Terrestrial Habitats

Biodiversity Areas and Corridor

PHS maps a biodiversity area and corridor approximately 300 feet southeast of the upland HDD entry point across the railroad tracks. Biodiversity areas and corridors are identified based on large intact blocks of habitat providing pathways for the movement, shelter, breeding areas, and gene flow of sensitive wildlife (Azerrad 2023). The area is identified as a priority terrestrial habitat in Snohomish County Park Lands due to the heavily vegetated intact parcels, and the presence of Coho salmon and resident coastal cutthroat utilizing *Pigeon Creek*.

The biodiversity area is a forested wilderness following *Pigeon Creek* and surrounded by urban development. The upland portion of the biodiversity area is classified as Vancouverian coastal rainforest with no old-growth timber. The area is owned by the City of Everett and is managed as Forest Park. The park has trails and infrastructure for public recreation.

Project design using HDD and BMPs are anticipated to have no adverse effects on the biodiversity area that lies upland and across the railroad tracks from the project site.

No net loss of biodiversity areas and corridors is anticipated.

3.2. Species of Concern

The significance of a species of concern and their associated habitats can vary between federal, state, and local jurisdictions. National Marine Fisheries Service (NMFS) and Washington Department of Fish and Wildlife (WDFW) Priority Habitats and Species (WDFW 2024 PHS) species of concern are listed in Table 2.

Table 2: Species of concern that may be near the project site.

Species	Significance	Occurrence	Impact
Rockfish	ESA listed	Yes	NNL
Salmonids	ESA listed, Local importance	Yes	NNL
Dungeness Crab	Vulnerable Aggregations	Yes	NNL



Cetaceans	ESA listed	Yes	NNL
-----------	------------	-----	-----

3.2.1. Salmonids

Multiple species of ESA-listed salmonid fish are presumed to use waters surrounding *Puget Sound* during various life cycle stages. These species include *Puget Sound* DPS steelhead (*Oncorhynchus mykiss*) listed as threatened under the ESA, updated April 14th, 2014 (79 FR 20802); *Puget Sound* bull trout (*Salvelinus confluentus*) listed as threatened under the ESA, updated November 11th 1999 (64 FR 58910); Hood Canal summer-run chum salmon (*Oncorhynchus keta*) listed as threatened under the ESA, updated April 14th, 2014 (79 FR 20802); and *Puget Sound* ESU Chinook salmon (*Oncorhynchus tshawytscha*) listed as endangered under the ESA, updated April 14th, 2014 (79 FR 20802). Endangered Chinook salmon may be of particular conservation concern as they use the nearby coastlines for growth and maturation during their outmigration from their natal freshwater streams.

Two additional salmonids are documented to occur in *Pigeon Creek* near the project site: Coho salmon (*Oncorhynchus kisutch*) and resident coastal cutthroat trout (*Oncorhynchus clarkii clarkii*). Coho are one of the five Pacific salmon species and sea-run cutthroat trout are a subspecies of the freshwater resident. Neither local species are an ESA listed species in *Puget Sound*.

Like other Pacific salmonids, coastal cutthroat trout are anadromous, living in freshwater streams and rivers as juveniles before migrating out to sea to feed and grow. Unlike Pacific salmon, coastal cutthroat trout may not die after spawning and return to a marine environment. Some coastal cutthroat trout may move between a marine environment and their natal stream to spawn more than once in their lives. Coho spawn in small streams with cool, consistent water flow and stable gravel substrates and coastal cutthroat trout will spawn in smaller creeks, rivers, or tributaries of larger rivers with small to moderate sized gravel (Pauley et al 1989).

Both Coho salmon and coastal cutthroat trout are documented to inhabit *Pigeon Creek*, which empties into *Puget Sound* through the project parcel’s *Pigeon Creek Beach* nearshore habitat. Juvenile salmonids, including Coho, coastal cutthroat trout and the endangered Chinook salmon, may use the nearshore areas as important migratory habitat that includes finding prey, such as forage fish and insects. These juvenile salmonids may use nearshore aquatic vegetation such as kelp and eelgrass for foraging and cover during their migration to the open ocean (Herrera and the Watershed Company, 2011). The documented patchy fringe eelgrass bed over 650 feet southeast of the project site could provide prey habitat and thus, foraging opportunities for juvenile salmon.



Sound producing project elements are proposed and include horizontal directional drilling (HDD). These sounds are anticipated to be non-injurious at close range but may result in minimal and temporary behavioral disturbance to individual salmon present at the project location. Temporary disturbance of submerged aquatic vegetation is not proposed, as none has been observed at the Port of Everett project site. HDD installation techniques will allow the proposed cable to make landfall via the conduit that extends approximately 1000 feet from the shore.

No net loss of salmonids is anticipated.

3.2.2. Rockfish

There are 36 species of rockfish (*Sebastes sp.*) found in the *Puget Sound* and *Georgia Basin* areas. Populations in the *Puget Sound* have decreased significantly in the last century due to overfishing and loss of habitat quality (Palsson et al. 2009, Williams et al. 2010). *Puget Sound/Georgia Basin* Distinct Population Segments (DPS) of yelloweye rockfish (*Sebastes ruberrimus*) are listed as threatened, and bocaccio (*Sebastes paucispinis*) as endangered under the ESA, which was made effective on July 27, 2010 (75 FR 22276).

Rockfish are viviparous, giving live birth to larval young. Larvae can inhabit the full water column but mostly occur in the upper 262 feet (Love et al. 2002, Weis 2004). Juvenile yelloweye rockfish typically settle in areas with steep rough terrain with rocky boulders or bedrock and at depths greater than 98 feet and they do not typically occur in shallow nearshore waters (Richards 1986, Yamanaka et al. 2006, Love et al. 2002, Palsson et al. 2009). Juvenile bocaccio rockfish move from open waters to settle onto nearshore benthic habitats. Juvenile yelloweye and bocaccio rockfish have rarely been documented in Puget Sound (Palsson et al. 2009, Obaza et al. 2021).

Adult yelloweye and bocaccio rockfish generally live at depths from approximately 100 to 1,400 feet (Orr et al. 2000, Love et al. 2002). Adults are often found in steep and rough habitats with features such as rocky outcroppings, kelp, bedrock, and areas dominated by cobble-boulder fields. (Yoklavich et al. 2000, Love et al. 2002, Anderson and Yoklavich 2007, Haldorson and Richards 1987, Matthews 1989). Yelloweye rockfish remain near the bottom and have relatively small home ranges, while some bocaccio rockfish have larger home ranges, move long distances, and spend time suspended in the water column (Demott 1983, Love et al. 2002, Friedwald 2009).

Much of the waters of *Possession Sound* are designated as nearshore critical habitat for bocaccio rockfish (50 CFR 226.224), excluding the *Snohomish River* outfall into *Puget Sound* around the City of Everett. Juvenile bocaccio rockfish have not been documented within the Georgia Basin in recent years (Drake et al. 2010), and suitable habitat may not occur near the project site due to a lack of rocks and kelp in the area. Adult listed rockfish are unlikely to be



in the nearshore shallow waters around the submarine cable proposed route and landfalls of *Possession Sound* because of the lack of appropriate habitat needs.

Impacts from the submarine conduit and cable installation will be temporary at both the Hat Island and Port of Everett project sites. In the vicinity where the HDD will daylight onto the seabed, there will be temporary disturbance of the substrate and may be an increase in local turbidity. Increased turbidity is anticipated to dissipate within a couple of tidal cycles. There may also be a temporary increase in noise pressure. Noise impacts are not anticipated to be injurious, even at close range, and the cable installation activities will be done in such a way that any rockfish in the area will be able to move away from the project site if disturbed.

No net loss of rockfish is anticipated.

3.2.3. Marine Mammals

Marine mammals found in Washington state include whales, dolphins, porpoise, seals, sea lions, and sea otters. All marine mammals are protected by the Marine Mammal Protection Act (MMPA), and some have protection under the Endangered Species Act (ESA). Gray whales, humpback whales, southern resident killer whales, and sea otters are federally or state ESA-listed marine mammals. Sea otters are found in the western section of the Strait of Juan de Fuca and the northern section of the Washington outer coast. The listed whales are frequently sighted in the *Puget Sound* area.

Gray whales (*Eschrichtius robustus*) are a medium-sized baleen whale that can weigh up to 45 tons and grow up to 50 feet in length. There are two regional populations in the *Pacific Ocean*, the endangered Western North Pacific stock and the delisted Eastern North Pacific stock (WDFW 2024 GW). A small group of the Eastern stock of gray whales, known as the Sounders, migrate into the *Puget Sound* in the spring to forage on ghost shrimp in shallow muddy bays mostly near Whidbey Island, Camano Island, and Everett (Cascadia Research Collective 2023). Gray whales may be seen within the proposed cable route in *Possession Sound* during the winter and spring. The proposed project and HDD daylighting offshore is not anticipated to impact gray whales in the area. If directed by the agencies, the HDD drilling could be completed before December when gray whales tend to start congregating and foraging in the area.

Humpback whales (*Megaptera novaeangliae*) are large baleen whales that can weigh up to 40 tons and grow up to 60 feet in length. There are three distinct population segments (DPSs) of humpbacks within Washington, and their habitat geographical range encompasses the entirety of the *Salish Sea* and outer coast of Washington (WDFW 2023 HW). Due to their size and method of foraging, humpback whales tend to prefer deeper, more open waters. According to the Orca Network, there have been more than four humpback whale sightings in south *Possession Sound* in the past two years (Orca Network 2024). Humpback whales may be



seen within the deeper parts of the proposed cable route in *Possession Sound* but unlikely in the shallower waters near HDD exit points.

The killer whale (*Orcinus orca*) is a medium-sized toothed whale that can weigh up to 11 tons and grow up to 32 feet in length. Killer whales in the Eastern North Pacific region are classed as offshore, transient (mammal-eating or Bigg’s), and resident (fish-eating) (NOAA 2023 KW). Killer whales are geographically distributed throughout the world and can be found within the marine waters of Washington state (WDFW 2023 KW). The *Salish Sea* resident killer whales are divided into two subgroups: northern and southern. The northern resident killer whales occur in the northern section of the *Salish Sea* and into Southeast Alaska. The southern residents (SRKW) reside mostly within *Puget Sound* and nearby coastal waters. These two distinct populations are structured around matriline and individuals have not been documented to reside within the other’s matriline. Over the past few decades, the northern resident population has grown to approximately 300 whales, whereas, the SRKW population has remained precariously low. Recent research has found that the two populations hunt prey differently (Tennessen 2023).

The historical minimum population size of southern resident killer whales was estimated at approximately 140 animals. The population has declined to the current population of approximately 75 individuals due to live capture for use in marine mammal parks; a lack of food, namely Chinook salmon; environmental contaminants; vessel traffic; and under-water noise (NOAA 2023 KW). SRKW were federally listed as endangered under the Endangered Species Act (ESA) in 2006 (70 FR 69903). The transient and offshore populations are stable or increasing, although the species is broadly listed as endangered in Washington state due to the status of the imperiled Southern Residents (WDFW 2023 KW).

Table 3 uses The Whale Museum’s (TWM) Orca Master dataset and shows the total sighting days from 1999 to 2022 of southern resident killer whales (SRKW) within the quadrate affected by the project’s underwater sound for the Port of Everett cable landfall. The number of sighting days in quadrate 386 during the proposed work window months of July 15th to February 15th totals 128.

Activities of an in-water project that may pose potential impacts to SRKW and their critical habitats are underwater noise

Table 3. Southern resident killer whale sightings during the proposed work window (NOAA and TWM 2024).

Month	Sightings in Quadrate 386, south <i>Possession Sound</i>
July	1
August	5
September	7
October	25
November	36
December	27
January	16
February	11
Total	128



greater than the assumed background noise for Puget Sound of 120 dB, often associated with pile driving and rock drilling. No pile driving or rock drilling is proposed for this project. The HDD sound is not expected to produce any consequential noise because the drilling occurs beneath the seafloor substrate. No long-term changes to aquatic habitats are proposed. Furthermore, the proposed project is designed to avoid or minimize impacts to nearby fish and wildlife critical habitats with HDD and by utilizing BPMs outlined in Section 5.1 Conservation Measures.

No net loss of ESA-listed marine mammals is anticipated.

3.2.4. Dungeness Crab

Many species of crab can be found in the waters around the San Juan Islands with the most economically valuable being the Dungeness crab (*Cancer magister*). Dungeness crabs are found from California to Alaska. Washington's commercial crab grounds extend from the Columbia River to Cape Flattery near Neah Bay and include the estuary of the Columbia River, Grays Harbor, and Willapa Bay and within Puget Sound from Everett north to the Canadian border (WDFW 2023 DC). A decline in Dungeness crab since 2013 necessitated the first full seasonal "personal use" harvest closures in 2018, and since 2015 the number of closures has increased in South-Central Puget Sound and Hood Canal (Velasquez 2022). Due to the population decline in Puget Sound, WDFW has identified Dungeness crab as a priority species under WDFW priority habitat and species program.

Dungeness crabs move inshore during the molting and mating season (Diamond and Hankin 1985). Males mate with recently molted females in the late spring and summer. Eggs are not immediately fertilized, and females can store sperm until eggs are fully developed or up to 2.5 years (Hankin et al. 1989). After hatching, larvae are planktonic for about 3 to 4 months and metamorphose through six stages until settlement. Juveniles prefer nearshore shallow estuarine areas with protective structures such as pilings or woody debris and primarily feed on fish, shrimp, mollusks, and crustaceans (Fisheries and Ocean Canada 2013). Adults prefer sandy or muddy substrate, eelgrass beds, and feed primarily on bivalves, crustaceans, and fish (Garth and Abbott 1980, Stevens et al. 1982). Along the Pacific coast, Dungeness crab live in the intertidal zone out to a depth of 750 feet, most frequently occurring deeper than 164 feet. The maximum life expectancy of Dungeness crab is 8-13 years (Kashef 2015). Threats to Dungeness crab include low dissolved oxygen levels, fluctuations in temperature and salinity, fisheries, loss or alteration to habitat, and pollutants. Early life stages are most likely to be influenced by human activities due to their reliance on estuarine habitats and high sensitivity to toxins (Dethier 2006).

Utilization of horizontal directional drilling (HDD) and the subsequent submarine power cable installation is anticipated to temporarily disturb the seabed in the vicinity of the Port of Everett parcel. These disturbances may temporarily increase turbidity and noise pressures at the project site during installation. Noise impacts from HDD are not anticipated to be



injurious, even at close range, and the power cable replacement activities will be done in such a way that crabs in the area will be able to move away from the project site if disturbed. Increased turbidity is anticipated to dissipate within a couple of tidal cycles.

No net loss of Dungeness crab is anticipated.

4. Cumulative Impacts Assessment

The following are potential impacts associated with proposed project activities, followed by conservation measures and best management practices (BMPs) designed to minimize or eliminate such impacts.

4.1. Direct Impacts

1. Potential of deleterious materials entering the water during construction activities.
2. Noise disturbances to listed species during submarine cable installation activities including sounds during the HDD procedures from shore and into the nearshore habitat.
3. Increased turbidity due to the HDD installation of the new submarine cable, which should disperse or settle with a few tidal cycles.
4. Potential direct physical contact of animals or habitats with, or indirect exposure to, oil discharge or other hazardous substances.
5. Addition of hard substrate to the seabed.

5. Mitigation Procedures for Critical Areas

Shoreline development, land uses, structures and activities must meet the no net loss requirement of WAC 173-26-186(8)(b). If project proposals do not comply with the critical area protections in Everett Municipal Code, applicants must submit a mitigation sequence analysis to the City of Everett for approval. Mitigation measures must be applied in the following sequence. The applicant must demonstrate that each mitigation action is not feasible or applicable before proceeding to the next option or action:

5.1. Conservation Measures

The potential direct and indirect impacts of the proposed project can be minimized by the following best management practices (BMPs):

- 1) Access to construction sites will be from the existing road and parking lot within the Port of Everett lot and the construction barge.
- 2) Situating the barge such that it does not ground out during installation.
- 3) Prefabricated project components will be used to reduce the duration of noise and barge activity required for submarine cable installation.
- 4) The avoidance of nearshore habitat and contaminated substrate at the Port of Everett with the use of HDD methods will minimize impacts.



- 5) No deleterious material will enter state waters.
- 6) Equipment will be kept in good running order and engines will be run only while needed to help reduce noise and the possibility of deleterious materials entering the water column or the shoreline jurisdiction.
- 7) Disposal of all waste material will be done appropriately at an approved upland disposal site.
- 8) Installation activities will take place at compatible tides during daylight hours to ensure that equipment does not ground out and installations are efficient.
- 9) Approved in-water work windows will be implemented and work is expected to take up to a month.
- 10) Spill prevention and clean-up plans will be in place for this activity as a safeguard against unexpected, accidental contamination. If a spill does occur that causes fish or other wildlife to be in obvious distress, project activity will immediately be halted and a WDFW Habitat biologist will be notified.
- 11) Construction activities will include the implementation of best management practices designed to limit or eliminate excess stormwater runoff during upland construction activities.
- 12) Erosion control and runoff treatment and prevention measures will include the minimum requirements as outlined in the Everett Municipal Code.
- 13) All construction will be done in accordance with the City of Everett's Municipal Code and Snohomish County Department of Health and Community Development building permits.

It is expected that the conservation measures and best management practices established for this project will limit potential disturbance to shoreline areas caused by construction activities. This will minimize the impact on all habitat and conservation areas in both the project site and nearby habitats.

5.2. Avoid Impacts

Avoiding all impact during project activities is not possible, however, installing the proposed submarine cable into a conduit that has been installed using HDD methods will allow for avoidance of the freshwater streams and nearshore habitats in the project site vicinity and will contribute to the reduction of impacts.

5.3. Minimize Impacts

Access to the terrestrial project site will occur through the existing access road to the proposed site at the Port of Everett lot. Access to the nearshore habitat and marine setting will primarily occur from the construction barge.

Temporary increased sediment disturbance may occur during HDD installation of the conduit and subsequent laying of the submarine cable. Although turbidity may increase locally, it is expected to dissipate within the next couple of tidal cycles and potential impacts to critical areas are expected to be minimal or non-existent with best management practices in place. In-water work windows



will be observed for the protection of sensitive salmonids and forage fish that may be utilizing the waters near the project site.

5.4. Mitigate Impacts

Mitigation measures are used to repair, rehabilitate, or restore the affected environment to the conditions existing at the time of the initiation of the project or activity.

Based on the project design and scope, it is expected that any long-term impacts from the cable installation will be negligible. No mitigation is proposed.

5.5. Reduce or Eliminate Impacts Over Time

Based on the project design and scope, it is expected that any long-term impacts from the cable installation will be negligible. Avoidance measures and best management practices have been developed to minimize potential construction impacts, which will persist only during the installation activities. Over time, it is anticipated that the new cable may self-bury, making its presence virtually indiscernible.

6. Conclusion

The above narrative contains information with regards to critical area habitats and species of concern potentially impacted by project activities. These include water quality/quantity and fish and wildlife habitat. Due to the project design, and provided that all recommendations described in this report are followed, **no net loss** of City of Everett Fish and Wildlife Habitat and Conservation Areas is expected.

This document hereby certifies that the information provided in this form is complete, true, and correct to the best of our knowledge based on the site visit on June 11, 2023, and documents given and accessed. The findings in this report were based on observations of conditions at the time of the site visit and are provided for the use of the named recipient only and are not intended for use by other parties for any purpose. This report does not guarantee agency concurrence or permit approval.



7. References

- Allen, J. and G. Smith. 1988. Atlas and zoogeography of common fishes in the Bering Sea and northeastern Pacific. U.S. Department of Commerce. NOAA Technical Report NMFS-66, 151 p.
- Anderson, T. and M. Yoklavich. 2007. Multiscale habitat associations of deepwater demersal fishes off central California. *Fishery Bulletin*. 105(2):168–179.
- Azerrad, J. M., J. L. Michalak, and T.P. Johnson. 2023. PHS Local Government User Guide: Biodiversity Areas and Corridors Map. Habitat Program, Washington Department of Fish and Wildlife, Olympia, Washington.
- Beamer, E. and K. Fresh. 2012. Juvenile salmon and forage fish presence and abundance in shoreline habitats of the San Juan Islands, 2008-2009: Map applications for selected fish species. Prepared for the San Juan County Department of Community Development and Planning, and the San Juan County Marine Resources Committee, Friday Harbor, WA.
- Cascadia Research Collective. 2023. Projects. North Puget Sound Gray Whales. [Accessed September 2023]. <https://cascadiaresearch.org/project/north-puget-sound-gray-whale-photo-id-and-feeding-study/>.
- DeMott, G. 1983. Movement of tagged lingcod and rockfishes off Depoe Bay, Oregon. Master of Science, Oregon State University.
- Dethier, M. 2006. Native Shellfish in Nearshore Ecosystems of Puget Sound. Puget Sound Nearshore Partnership Report No. 2006-04, Seattle, WA.
- Diamond, N. and D. Hankin. 1985. Movements of adult female Dungeness crabs (*Cancer magister*) in Northern California based on tag recoveries. *Canadian Journal of Fisheries and Aquatic Sciences*. 42: 919-926.
- FEMA. 2024. Federal Emergency Management Agency. Flood Hazard Zones: FEMA Coastal Flood Hazard Analysis and Mapping Guidelines Focused Study Report. [Accessed June 2023]. https://www.fema.gov/media-library-data/20130726-1541-20490-5411/frm_p1zones.pdf
- Fisheries and Ocean Canada. 2013. Dungeness Crab Biology. [Accessed March 2023]. <https://www.dfo-mpo.gc.ca/species-especes/profiles-profil/dungeness-crab-crabe-dormeur-eng.html>.
- Friedwald, J. 2009. Causes and consequences of the movement of temperate reef fishes. PhD Dissertation, University of California, Santa Cruz, CA. 89 pages.
- Froese, R. and D. Pauly. 2024. Editors. FishBase. Version 2/2024. [Accessed April 2024]. www.fishbase.org.



- Garth, J. and D. Abbott. 1980. Brachyura: The true crabs. In: Morris, H., Abbott, D., and Haderlie, E. (Eds.), Intertidal Invertebrates of California. Stanford University Press. Stanford, California. pp 594–630.
- Haldorson, L. and L. Richards. 1987. Habitat use and young of the year copper rockfish (*Sebastes caurinus*) in British Columbia. Proceedings of the International Rockfish Symposium. Vol. 87. Fairbanks, AK.: Alaska Sea Grant Report. p. 129–141.
- Hankin, D., N. Diamond, M. Mohr, and J. Ianelli. 1989. Growth and reproductive dynamics of adult female Dungeness crabs (*Cancer magister*) in northern. ICES Journal of Marine Science. 46: 94-108.
- Herrera and The Watershed Company. 2011. Best Available Science for Marine Fish and Wildlife Habitat Conservation Areas. In San Juan County Best Available Science Synthesis. Reference Number: 100814.
- HIAC. 2024. Hat Island Community Association, Inc. [Assessed June 2024]. <https://hatisland.org/>.
- Kashef, N. 2015. Monterey Bay Aquarium Seafood Watch, [Accessed March 2023]. https://www.seafoodwatch.org/globalassets/sfw-data-blocks/reports/c/mba_seafoodwatch_dungeness_crab_report.pdf.
- Love, M., M. Yoklavich, and L. Thorstein. 2002. The rockfishes of the Northeast Pacific. University of California Press. 404 pages.
- Map Everett. 2024. Map Everett Online Map Viewer. Everett Community, Planning and Economic Development. [Accessed June 2024]. <https://gismaps.everettwa.gov/apps/MapEverettDE/>.
- Matthews, K. 1989. A Comparative Study of Habitat Use by Young-of-the year, Subadult, and Adult Rockfishes on Four habitat Types in Central Puget Sound. Fishery Bulletin. U.S. Volume 88, pages 223 to 239.
- Mecklenburg, C., T. Mecklenburg, and L. Thorsteinson. 2002. Fishes of Alaska, 1037 p. American Fisheries Society, Bethesda, MD.
- Mofjeld, H. 1992. Subtidal sea level fluctuations in a large fjord system. Journal of Geophysical Research. Vol. 97 (C12) pp. 20191-20199.
- NOAA. 2023. [CS]. National Oceanic and Atmospheric Administration Fisheries. Species Directory. Coho Salmon. [Accessed May 2024]. <https://www.fisheries.noaa.gov/species/coho-salmon>.
- NOAA. 2023. [KW]. National Oceanic and Atmospheric Administration Fisheries. Species Directory. Killer Whale. [Accessed June 2023]. <https://www.fisheries.noaa.gov/species/killer-whale>.
- NOAA. 2024. [Sec 7]. National Oceanic and Atmospheric Administration Fisheries. ESA Section 7 Consultation Tools for Marine Mammals on the West Coast. [Accessed June 2023].



<https://www.fisheries.noaa.gov/west-coast/endangered-species-conservation/esa-section-7-consultation-tools-marine-mammals-west>.

NOAA and TWM. 2024. National Oceanic and Atmospheric Administration Fisheries and The Whale Museum. Southern Resident Killer Whale (SRKW) Sightings 1999-2022. [Accessed February 2024].

<https://noaa.maps.arcgis.com/apps/dashboards/d29b088d7b4849489c4338a4c3d36e4c>.

Obaza, A., A. Bird, J. Selleck, and D. Tonnes. 2021. Results from Young-of-the-Year Rockfish Surveys in the southern Salish Sea 2015-2020. Protected Resources Division. Puget Sound Ecosystem Branch. National Marine Fisheries Service. West Coast Region.

Orca Network. 2024. Sightings Archives. [Accessed May 2024]. <https://indigo-ukulele-jm29.squarespace.com/sightings-report-archive>.

Orr, J., M. Brown, and D. Baker. 2000. Guide to rockfishes (Scorpaenidae) of the genera *Sebastes*, *Sebastolobus*, and *Abelosebastes* of the northeast Pacific Ocean. Second Edition. United States Department of Commerce. NOAA Technical Memorandum. NMFS-AFSC-117. 47 pages.

Palsson, W., T. Tsou, G. Bargmann, R. Buckley, J. West, M. Mills, Y. Cheng, and R. Pacunski. 2009. The biology and assessment of rockfishes in Puget Sound. Washington Department of Fish and Wildlife, FPT 09-04, Olympia, WA.

Paul, J., A. Paul, T. Vogeler, and J. Doyle. 1997. Biological investigations on Pacific Sandfish (*Trichodon trichodon*) in the northern Gulf of Alaska. In Proceedings of the International Symposium on the Role of Forage Fishes in Marine Ecosystems. Anchorage, Alaska. University of Alaska Sea Grant College Program Report No. 97-01.

Pauley, G., K. Oshima, K. Bowers, and G. Thomas. 1989. Species profiles: life histories and environmental requirements of coast fishes and invertebrates (Pacific Northwest) Sea-run cutthroat trout. U.S. Fish and Wildlife. Serv. Biol. Rep. 82 (11.89). U.S. Army Corps of Engineers TR EL-82_4

Penttila, D. 2007. Marine Forage Fishes in Puget Sound. Puget Sound Nearshore Partnership Report No. 2007-03. Published by Seattle District, U.S. Army Corps of Engineers, Seattle, Washington.

Pietsch, T. and J. Orr, 1958- (2015). Fishes of the Salish Sea; a compilation and distributional analysis.

Port of Everett. 2018. Port of Everett- The First 100 Years. Pediment Publishing, a division of The Pediment Group, Inc.

Richards, L. 1986. Depth and habitat distributions of three species of rockfish (*Sebastes*) in British Columbia: observations from the submersible PISCES IV. Environmental Biology of Fishes. Volume 17(1), pages 13 to 21.



- Selden, K., and M. Baker. 2023. Influence of marine habitat on microplastic prevalence in forage fish and salmon in the Salish Sea. *Marine Pollution Bulletin*, 197, 115748.
- SCOPI. 2024. Snohomish County Online Property Information. Snohomish County Assessor. [Assessed June 2024]. <https://snohomishcountywa.gov/5414/Interactive-Map-SCOPI>.
- SnoPUD. 2024. Snohomish County Public Utilities District No. 1. [Assessed June 2024]. <https://www.snopud.com/>.
- State of Washington. 1959. Orders of the Director of Fisheries. Order 483.
- Stevens, B., D. Armstrong, and R. Cusimano. 1982. Feeding habits of the Dungeness crab (*Cancer magister*) as determined by the index of relative importance. *Marine Biology*. 72:135-145.
- Tennessen, J., M. Holt, B. Wright, M. Hanson, C. Emmons, D. Giles, J. Hogan, S. Thornton, and V. Deecke. 2023. *Behavioral Ecology*. Vol. 34, Issue 3, pgs 373-386. [Accessed September 2023]. <https://academic.oup.com/beheco/article/34/3/373/7069400>.
- USDA. 2009. United States Department of Agriculture. Natural Resources Conservation Service. Part 630 Hydrology National Engineering Handbook. Chapter 7: Hydrologic Soil Groups.
- USFWS. 2024. [CCT]. United States Department of Fish and Wildlife. Species. Coastal Cutthroat Trout. [Accessed May 2024]. <https://www.fws.gov/species/coastal-cutthroat-trout-oncorhynchus-clarkii-clarkii>.
- USFWS. 2024. [CS]. United States Department of Fish and Wildlife. Species. Coho Salmon. [Accessed May 2024]. <https://www.fws.gov/species/coho-salmon-oncorhynchus-kisutch>.
- USGS. 2018. United States Geological Survey. Water Science School. Science. Surface Water. [Assessed November 2023]. <https://www.usgs.gov/special-topics/water-science-school/science/surface-water>.
- Velasquez, D. 2023. Puget Sound Info. Puget Sound Indicators. Dungeness Crab Catch for Personal Use. [Accessed March 2023]. <https://www.pugetsoundinfo.wa.gov/Indicator/Detail/87/VitalSigns#:~:text=Since%202015%20an%20increasing%20number%20of%20harvest%20closures,this%20indicator%20is%20determined%20to%20be%20%E2%80%9Cgetting%20worse%E2%80%9D>.
- WDFW. 2024. [CCT]. Washington Department of Fish and Wildlife. Species and Habitats. Coastal cutthroat trout (resident) (*Oncorhynchus clarkii clarkii*). [Accessed May 2024]. <https://wdfw.wa.gov/species-habitats/species/oncorhynchus-clarkii-clarkii>.
- WDFW. 2024. [CS]. Washington Department of Fish and Wildlife. Species and Habitats. Coho salmon (Lower Columbia River ESU), (*Oncorhynchus kisutch* pop. 1). [Accessed May 2024]. <https://wdfw.wa.gov/species-habitats/species/oncorhynchus-kisutch-pop-1#conservation>.



- WDFW. 2024. [FF]. Washington State Department of Fish and Wildlife. Forage Fish Spawning Map. [Accessed May 2024].
<https://wdfw.maps.arcgis.com/home/webmap/viewer.html?webmap=19b8f74e2d41470cbd80b1af8dedd6b3>.
- WDFW. 2023. [DC]. Washington State Department of Fish and Wildlife. Fishing and Shellfishing. Commercial fishing. Commercial Dungeness crab fishery. [Accessed March 2023].
<https://wdfw.wa.gov/fishing/commercial/crab>.
- WDFW. 2023. [GW]. Washington State Department of Fish & Wildlife. Species and Habitat. Gray whale (*Eschrichtius robustus*). [Accessed June 2023]. <https://wdfw.wa.gov/species-habitats/species/eschrichtius-robustus>.
- WDFW. 2023. [HW]. Washington State Department of Fish & Wildlife. Species and Habitat. Humpback whale (*Megaptera novaeangliae*). [Accessed June 2023]. <https://wdfw.wa.gov/species-habitats/species/megaptera-novaeangliae>.
- WDFW. 2023. [KW]. Washington State Department of Fish & Wildlife. Species and Habitat. Killer whale (*Orcinus orca*). WDFW [Accessed June 2023]. <https://wdfw.wa.gov/species-habitats/species/orcinus-orca#desc-range>.
- WDFW. 2024. [PHS]. Washington State Department of Fish and Wildlife. Priority Habitats and Species (PHS) List. [Accessed May 2024]. <https://geodataservices.wdfw.wa.gov/hp/phs/>.
- WDNR. 2024. [FPAMT]. Washington State Department of Natural Resources. Forest Practices Application Mapping Tool. [Accessed October 2024]. https://fpamt.dnr.wa.gov/2d-view#activity?-13607957,-13604900,6101348,6102875?WADNR_PUBLIC_Public_Land_Survey!4!8!0!,WADNR_PUBLIC_FP_Trans!0!1!2!,WADNR_PUBLIC_FP_Misc!1!0!4!,WADNR_PUBLIC_FP_Water_Type!1!,WADNR_PUBLIC_FP_Hydro!1!3!,WADNR_PUBLIC_OCIO_Parcels!0!
- WDNR. 2024. [Hazards]. Washington State Department of Natural Resources. Washington Geologic Information Portal. Natural Hazards. [Accessed May 2024].
https://geologyportal.dnr.wa.gov/2d-view#natural_hazards?-14252374,-12686943,5619567,6428577.
- WDNR. 2024. [WNHP]. Washington State Department of Natural Resources. Washington Natural Heritage Program (WNHP) Data Explorer. [Accessed May 2024].
<https://experience.arcgis.com/experience/174566100f2a47bebe56db3f0f78b5d9/page/Rare-Plant-and-Ecosystem-Locations/>.
- WDOE. 2024. Washington State Department of Ecology. Stormwater Management Manual for Western Washington. Publication Number 24-10-013. Volume II. Pages 269-454.



- WDOE. 2024. [Atlas]. Washington State Department of Ecology. Coastal Atlas Map. [Accessed May 2024]. <https://fortress.wa.gov/ecy/coastalatlus/tools/Map.aspx>.
- WDOH. 2024. Washington State Department of Health. Shellfish Safety Information. [Accessed May 2024]. <https://fortress.wa.gov/doh/biotoxin/biotoxin.html>.
- Weis, L. 2004. The effects of San Juan County, Washington, marine protected areas on larval rockfish production. Master of Science thesis. University of Washington Seattle, WA. 55 pages.
- Williams, G., P. Levin, and W. Palsson. 2010. Rockfish in Puget Sound: An ecological history of exploitation. *Marine Policy* 34, pp. 1010-1020.
- WNTC. 2024. [CCT]. Western Native Trout Challenge. Coastal Cutthroat Trout. [Accessed May 2024]. <https://westernnativetrout.org/coastal-cutthroat-trout/>.
- Yamanaka, K., L. Lacko, R. Witheler, C. Grandin, J. Lothead, J. Martin, N. Olsen, and S. Wallace. 2006. A review of yelloweye rockfish (*Sebastes ruberimus*) along the Pacific coast of Canada: biology, distribution and abundance trends. Research Document 2006/076. Fisheries and Oceans Canada. 54 pages.
- Yang, M. and M. Nelson. 2000. Food Habits of the Commercially Important Groundfishes in the Gulf of Alaska in 1990, 1993, and 1996. U. S. Department of Commerce, NOAA Technical Memorandum. NMFS-AFSC 112, pp. 174.
- Yoklavich, M., H. Greene, G. Cailliet, D. Sullivan, R. Lea, and M. Love. 2000. Habitat associations of deep-water rockfishes in a submarine canyon: an example of a natural refuge. *Fishery Bulletin*. Volume 98, pp. 625-641.



8. Jen-Jay, Inc. Qualifications

Jen-Jay, Inc. was established in 1989 as a biological consulting firm focused on biological assessments, environmental permitting, conducting underwater and inter-tidal surveys, and commercial diving. The following staff conducted this assessment. A summary of their qualifications is provided.

Chris Betcher, Principal Biologist

Chris Betcher is a biologist with 38 years of experience conducting intertidal and underwater biological surveys and studies within Puget Sound. Chris conducts Eelgrass/Macroalgae Habitat, forage fish, and geoduck surveys; conducts studies for salinity near desalination plants; vegetation monitoring for mitigation and restoration sites; provides consultation for overwater structures, barge landings, and restoration projects; and provides management recommendations to support permit compliance and performance standards.

Credentials:

- BS, Marine Biology, Western Washington University, 1978
- WDFW certified for conducting forage fish surveys, 2002
- WDFW certified for conducting geoduck surveys, 1999

Kim Middleton, Lead Biologist and Permitting Specialist

Kim Middleton is a scientist with 38 years of research experience. Her biology background is grounded in ornithology. Kim possesses a thorough working knowledge of local, state, and federal permitting and plan requirements, including Washington state's SEPA and State Hydraulic Code and federal JARPA and NEPA processes. Kim conducts terrestrial and marine avian point count and behavioral surveys, critical area assessments, water quality sampling, vegetation monitoring of mitigation and restoration sites; prepares critical areas reports; and provides consulting for environmental compliance of overwater structures.

Credentials:

- BS, Biology and Chemistry, Western Washington University, 1980
- WDOE Certified Erosion and Sediment Control Lead (CESCL) 2023

Alise Newman, Biologist and Permitting Specialist


Alise Newman is a biologist with a background in terrestrial mammalogy and evolutionary development. Within the marine science field, Alise has experience working with federal agencies conducting intertidal eelgrass surveys, European green crab monitoring, forage fish surveys, water quality and amphibian monitoring, and larval fish identification.

Credentials:

- BS, Biology, University of Washington 2022
- WDFW certified for conducting forage fish surveys, 2022



SNOHOMISH COUNTY	
PUD	
PUBLIC UTILITY DISTRICT NO. 1	
WO	100045299
TASK	
SCALE	1"=2000'
DFTR	JTF
CHKR	
ENGR	
APVD	
DATE	3/17/2023



GENERAL PROJECT AREA
SCALE: 1"=2500'

GENERAL PROJECT DESCRIPTION

SNOHOMISH COUNTY PUBLIC UTILITY DISTRICT NO. 1 PROPOSES INSTALLATION OF A NEW SUB-SEA POWER CABLE . THE CABLE SPANS FROM UPLAND OF PORT OF EVERETT OWNERSHIP ACROSS POSSESSION SOUND APPROXIMATELY 6.3 MILES TO AN EXISTING POWER CONNECTION NEAR THE MARINA AT HAT ISLAND. BOTH LANDWARD ENTRY/EXIT POINTS WILL EMPLOY HORIZONTAL DIRECTIONAL DRILLING (HDD) AS SHOWN ON ATTACHED PROFILE SHEETS.

DATUM AND TIDAL INFORMATION

1. BASIS OF BEARINGS FOR THIS PROJECT IS GRID NORTH, WASHINGTON COORDINATE SYSTEM NORTH ZONE NAD 83 (2011): BASED ON GLOBAL NAVIGATION SATELLITE SYSTEM (GNSS) OBSERVATIONS.
2. VERTICAL DATUM IS MEAN LOWER LOW WATER (MLLW), NOAA STATION 9447659 EVERETT, WA EPOCH 1983-2001. TIDAL DATUMS AND SUBSEQUENT CONVERSIONS ARE AS FOLLOWS:

DATUM	ELEVATION
MEAN LOWER LOW WATER (MLLW)	0.00
NAVD88	2.03
MEAN LOW WATER (MLW)	2.80
MEAN HIGH WATER (MHW)	10.21
MEAN HIGHER HIGH WATER (MHHW)	11.09

3. EXTREME LOW TIDE (ELT) AS SHOWN HEREON, AND AS DEFINED BY PUBLISHED DNR GUIDANCE MEANS THE LINE AS ESTIMATED BY THE FEDERAL GOVERNMENT BELOW WHICH IT MIGHT REASONABLY BE EXPECTED THAT THE TIDE WOULD NOT EBB. IN THE PUGET SOUND AREA OF WASHINGTON STATE, THIS LINE IS ESTIMATED BY THE FEDERAL GOVERNMENT TO BE A POINT IN ELEVATION 4.50 FEET (PLUS OR MINUS 0.5 FEET) BELOW THE DATUM PLANE OF MEAN LOWER LOW WATER, (0.0).
4. ALL DISTANCES AND ELEVATIONS SHOWN HEREON ARE IN FEET AND DECIMALS THEREOF.
5. TERRESTRIAL AREAS OF HAT ISLAND WERE SURVEYED AND MAPPED BY HARMSSEN LLC IN DECEMBER AND JANUARY OF 2019.
6. BATHYMETRIC DATA IS TETRATECH BATHYMETRIC SURVEY DATED ~~XXXXX~~.
7. SNOHOMISH WATERSHED KELP AND EEL GRASS PROTECTION ZONE SHOWN AS DESCRIBED ON COMMISSIONER'S ORDER NUMBER 202201, SIGNED MARCH 16, 2022.
8. ANCHOR AREA IS COORDINATE PROVIDE BY CFR 110.230 (5) PORT GARDNER GENERAL ANCHORAGE.


SHEET INDEX

SHEET	TITLE
P1	COVER SHEET
P2	HAT ISLAND PLAN AND PROFILE
P3	PORT OF EVERETT PLAN AND PROFILE
P4	SUB-SEA CABLE PLAN AND PROFILE
P5	SUB-SEA CABLE PLAN AND PROFILE
P6	PORT OF EVERETT DETAIL AREA
P7	HAT ISLAND DETAIL AREA
P8	LEGEND AND ABBREVIATIONS

REVISIONS	No	DATE	BY
HAT ISLAND TO PORT OF EVERETT CABLE CROSSING PERMIT SET COVER SHEET			
REV	DRAWING		
0	P1		


DRAFT
FOR REVIEW

SNOHOMISH COUNTY	
PUD	
PUBLIC UTILITY DISTRICT NO. 1	
WO	100045299
TASK	
SCALE	1"=150'
DFTR	JTF
CHKR	
ENGR	
APVD	
DATE	3/17/2023



PLSS DATA

TERRESTRIAL PORTIONS OF THIS SITE ON HAT (GEDNEY) ISLAND RESIDE IN THE PLATS OF HAT ISLAND DIVISIONS C & D, AS RECORDED UNDER AUDITOR'S FILE NUMBERS 1628702 AND 1560007, RECORDS OF SNOHOMISH COUNTY, WA. ALL IN SECTION 8, T 29N, R 4E, W.M.





CABLE PROFILE
SCALE 1"=150 HORIZONTAL/VERTICAL

DRAFT
FOR REVIEW

REVISIONS	BY	
	DATE	
HAT ISLAND TO PORT OF EVERETT CABLE CROSSING PERMIT SET HAT ISLAND PLAN & PROFILE		
REV	DRAWING	
0	P2	

SNOHOMISH COUNTY	
PUD	
PUBLIC UTILITY DISTRICT NO. 1	
WO	100045299
TASK	
SCALE	1"=150'
DFTR	JTF
CHKR	
ENGR	
APVD	
DATE	3/17/2023





REVISIONS	
BY	
NO	DATE

HAT ISLAND TO PORT OF EVERETT
 CABLE CROSSING
 PERMIT SET
 PORT OF EVERETT PLAN & PROFILE

REV	DRAWING
0	P3

WO	100045299
TASK	
SCALE	1"=150'
DFTR	JTF
CHKR	
ENGR	
APVD	
DATE	3/17/2023



SUB-SEA CABLE PROFILE
SCALE 1"=1000' HORIZONTAL / 1"=200' VERTICAL

REVISIONS	
BY	
DATE	

HAT ISLAND TO PORT OF EVERETT
CABLE CROSSING
PERMIT SET
SUB-SEA CABLE PLAN & PROFILE

DRAFT
FOR REVIEW

REV	DRAWING
0	P4

SEE SHEET P4
N:367,595
E:1,288,310

SEE SHEET P5
N:357901
E:1296469

POSSESSION SOUND

WO	100045299
TASK	
SCALE	1"=150'
DFTR	JTF
CHKR	
ENGR	
APVD	
DATE	3/17/2023



REVISIONS

BY

No DATE


HAT ISLAND TO PORT OF EVERETT
CABLE CROSSING
PERMIT SET
SUB-SEA CABLE PLAN & PROFILE

REV	DRAWING
0	P5



SUB-SEA CABLE PROFILE
SCALE 1"=1000' HORIZONTAL / 1"=200' VERTICAL

DRAFT
FOR REVIEW



PROPOSED EASEMENTS

- A** 15-FT EASEMENT EXTENDING TO PORT OF EVERETT PROPERTY LINE (INNER HARBOR LINE) FOR CABLE CROSSING OVER AND UNDER PORT PROPERTY
- B** 15-FT WIDE EASEMENT OVER PORT OF EVERETT PROPERTY FOR OVERHEAD WIRE CONNECTION FROM NEW POLE TO EXISTING POWER LINE.
- C** TEMPORARY CONSTRUCTION EASEMENT OVER THE SOUTHWESTERLY 150 FEET OF THE EXISTING FENCED BONE YARD.
- D** EXISTING 10-FT WIDE POWER LINE EASEMENT FOR THE EXISTING POWER CORRIDOR


DRAFT
FOR REVIEW

REVISIONS

No DATE BY

HAT ISLAND TO PORT OF EVERETT
CABLE CROSSING
PERMIT SET
PORT OF EVERETT DETAIL AREA


REV	DRAWING
0	P6



WO	100045299
TASK	
SCALE	1"=30'
DFTR	JTF
CHKR	
ENGR	RKS
APVD	
DATE	3/17/2023

No	DATE	BY	REVISIONS

HAT ISLAND TO MISSION BEACH CABLE CROSSING PERMIT SET	
HAT ISLAND DETAIL AREA	
REV	DRAWING
0	P7



PERMIT SET

LEGEND

EXISTING

- UTILITY POLE ANCHOR
- UTILITY POLE
- TRANSFORMER
- LIGHT POST
- POWER VAULT
- BOLLARD
- POWER METER
- JUNCTION BOX
- PILING
- STORM DRAIN CATCH BASIN
- STORM DRAIN MANHOLE
- AREA DRAIN
- SANITARY SEWER MANHOLE
- WATER METER
- WATER VALVE
- FIRE HYDRANT
- FAUCET
- IRRIGATION VALVE
- WELL HEAD
- MAIL BOX
- TELEPHONE MANHOLE
- TELEPHONE PEDESTAL/MARKER
- ALDER TREE
- CEDAR TREE
- PINE TREE
- DECIDUOUS TREE
- MADRONA TREE
- FLAG POLE
- SIGN

- CULVERT
- GAS LINE
- DITCH CENTERLINE
- STORM DRAIN
- SEWER LINE
- OVERHEAD POWER
- OVERHEAD TELEPHONE
- UNDERGROUND POWER
- UNDERGROUND TELEPHONE
- CHAIN LINK FENCE
- WOOD FENCE
- EXISTING SUB SEA CABLE

PROPOSED

- NEW HDD CABLE / SUB SEA CABLE
- CABLE AND CONDUIT IN TRENCH
- ELECTRIC TRANSFORMER
- JUNCTION BOX
- ELECTRIC SWITCH GEAR
- CABLE CROSSING DAY MARK
- POWER POLE

ABBREVIATIONS

- AFN - AUDITOR'S FILE NUMBER
- APN - ASSESSOR'S PARCEL NUMBER
- CONC - CONCRETE
- CB - CATCH BASIN
- CL - CENTERLINE
- CMP - CORRUGATED METAL PIPE
- CPP - CORRUGATED PLASTIC PIPE
- CONC - CONCRETE
- DIA - DIAMETER
- ELT - EXTREME LOW TIDE
- ESMT - EASEMENT
- FDC - FIRE DEPARTMENT CONNECTION
- FT - U.S. SURVEY FEET
- G.E. - GRATE ELEVATION
- HDD - HORIZONTAL DIRECTIONAL DRILLING
- I.E. - INVERT ELEVATION
- LS - LAND SURVEYOR
- MHW - MEAN HIGH WATER
- MHHW - MEAN HIGHER HIGH WATER
- MLLW - MEAN LOWER LOW WATER
- MLW - MEAN LOW WATER
- OHWM - ORDINARY HIGH WATER MARK
- PVC - POLYVINYL CHLORIDE
- R.O.- REVERSE OSMOSIS
- SD - STORM DRAIN
- SS - SANITARY SEWER
- SSMH - SANITARY SEWER MANHOLE
- STA - STATION
- TYP - TYPICAL
- YD - YARD DRAIN

WO	100045299
TASK	
SCALE	NTS
DFTR	JTF
CHKR	
ENGR	RKS
APVD	
DATE	3/17/2023

No	DATE	BY	REVISIONS

HAT ISLAND TO MISSION BEACH
CABLE CROSSING
PERMIT SET
LEGEND & ABBREVIATIONS

REV	DRAWING
0	P8

PERMIT SET



JEN-JAY, INC.

Preliminary Eelgrass Macro Algae Habitat Survey
Snohomish Public Utilities District – Hat (Gedney) Island Power Cable
11 June 2023

LOCATION: Between the northeastern shore of Hat Island and Pigeon Creek Beach area of Everett, WA.

PURPOSE: To survey the area for replacement of a failing submarine power cable.

TIME: 9:30 AM

VISIBILITY: 15' ±

DEPTH CALCULATIONS: Depth contours (Bathymetric Survey) were provided by others.

BOTTOM TYPE: The channel is entirely mud/sand with 0-12" rock nearshore on both landing sites.

VEGETATION: Eelgrass (*Zostera marina*) was observed on the Hat Island landing of the proposed cable location starting approximately 50 feet above MLLW and extending offshore for a total of 150 feet, approximately. On the Everett landing there was no observed eelgrass or macroalgae. On the Hat Island landing there is generally no macroalgae, with the exception of small amounts of filamentous green algae growing on small rocks in the nearshore. The accompanying drawings indicate where vegetation was observed.

SURVEY PATTERN: A single transect was swam by a diver along the proposed route. The Hat Island landing was surveyed for 300' to a depth of approximately -30'. The Everett landing was surveyed for 800' to a depth of approximately -30'. Observations were made every twenty feet, with the diver noting any observed vegetation within their visible range to either side. Additionally, a TOPCON HiPer VR GNSS rover receiver was used to map the boundaries of the eelgrass on the Hat Island landing of the proposed route.

Survey methods for this project are in accordance with the WDFW Eelgrass/Eelgrass Habitat Interim Survey Guidelines revised in June 2008 and WAC 220-660-35, and follow the Preliminary Survey and Tier 1 survey methods outlined in Components of a Complete Eelgrass Delineation Report developed by the Army Corps of Engineers (ACOE) dated January 9, 2018. Eelgrass Delineation Method B was employed to determine the location of the edge of the eelgrass bed. A single linear transect was used to assess vegetation at the project site, as the power cable has a narrow, linear impact zone. The deviation from the survey guidelines was approved by the WDFW Area Habitat Biologist prior to conducting the eelgrass/macroalgae survey.

VERTEBRATE and INVERTEBRATE SPECIES: None noted.



JEN-JAY, INC.

FORAGE FISH HABITAT: There is WDFW documented sand lance spawning habitat located on the beach at the proposed Hat Island cable landfall. No documented forage fish spawning habitat is present at the Everett landfall, however, there are sand lance and surf smelt spawning habitats documented approximately 3500' to the southwest.

Any questions regarding this survey should be addressed to:

JEN-JAY DIVING, INC.

HAT ISLAND LANDFALL
17D E Marine View Dr
TPN: 00466300003001




SCALE: 1" = 40'

KEY

- = eelgrass
- = transects with eelgrass estimates; L = low density M = medium density H = high density 0 = no eelgrass
- #' MLLW = contour lines provided by others.

OBSERVED ALGAE KEY

- f. green = filamentous green
- 0 MA = no macroalgae



48.01954°N, 122.32046°W

48.01885°N, 122.32207°W

48.01910°N, 122.32150°W

Hat Island

WATERWARD EDGE OF EELGRASS BED

Possession Sound

Proposed Cable Route

Cable Crossing Sign

Sandy mud, 0-6" rock f. green 5% cover

IRREGULAR AND PATCHY INNER EDGE OF EELGRASS

PRELIMINARY EELGRASS MACROALGAE HABITAT SURVEY
 FOR: SNOHOMISH PUD
 BY: JEN-JAY INC.
 DATE: JUNE 11, 2023
 PAGE 1 OF 5

NOT CONSTRUCTION DRAWINGS
 DEPTH CONTOURS AND ORIENTATION TO
 LAND FEATURES ARE APPROXIMATE

EVERETT LANDFALL OVERVIEW


2890 Terminal Ave
TPN: 29042500400200

47.97164°N, 122.23372°W

PAGE 3 OF 5

PAGE 4 OF 5

PAGE 5 OF 5




SCALE: 1" = 100'

Possession Sound

47.97125°N, 122.23029°W

47.97122°N, 122.22998°W



KEY

OBSERVED ALGAE KEY

↓ = eelgrass

0 MA = no macro algae

⊕ = transects with eelgrass estimates:
L = low density
M = medium density
H = high density
0 = no eelgrass

⋯# MLLW = contour lines provided by others

PRELIMINARY EELGRASS MACROALGAE HABITAT SURVEY
FOR: SNOHOMISH PUD
BY: JEN-JAY INC.
DATE: June 11, 2023
PAGE 2 OF 5

NOT CONSTRUCTION DRAWINGS
DEPTH CONTOURS AND ORIENTATION TO
LAND FEATURES ARE APPROXIMATE

EVERETT LANDFALL



SCALE: 1" = 40'


KEY

- = eelgrass
- = transects with eelgrass estimates;
L = low density
M = medium density
H = high density
0 = no eelgrass
- #' MLLW = contour lines provided by others

OBSERVED ALGAE KEY

0 MA = no macroalgae

47.97164°N, 122.23372°W



Proposed Cable Route


Possession Sound

EXISTING CABLE NOT ASSOCIATED WITH PROJECT

PRELIMINARY EELGRASS MACROALGAE HABITAT SURVEY
FOR: SNOHOMISH PUD
BY: JEN-JAY INC.
DATE: JUNE 11, 2023
PAGE 3 OF 5

NOT CONSTRUCTION DRAWINGS
DEPTH CONTOURS AND ORIENTATION TO
LAND FEATURES ARE APPROXIMATE

EVERETT LANDFALL




SCALE: 1" = 40'

KEY

- = eelgrass
- = transects with eelgrass estimates;
L = low density
M = medium density
H = high density
0 = no eelgrass
- # MLLW = contour lines provided by others

OBSERVED ALGAE KEY

0 MA = no macroalgae




Proposed Cable Route

EXISTING CABLE NOT ASSOCIATED WITH PROJECT

PRELIMINARY EELGRASS MACROALGAE HABITAT SURVEY
FOR: SNOHOMISH PUD
BY: JEN-JAY INC.
DATE: JUNE 11, 2023
PAGE 4 OF 5

NOT CONSTRUCTION DRAWINGS
DEPTH CONTOURS AND ORIENTATION TO
LAND FEATURES ARE APPROXIMATE

EVERETT LANDFALL




SCALE: 1" = 40'

KEY

- = eelgrass
- = transects with eelgrass estimates;
L = low density
M = medium density
H = high density
0 = no eelgrass
- # MLLW = contour lines provided by others

OBSERVED ALGAE KEY

0 MA = no macroalgae



EXISTING CABLE
NOT ASSOCIATED
WITH PROJECT

PRELIMINARY EELGRASS MACROALGAE HABITAT SURVEY
FOR: SNOHOMISH PUD
BY: JEN-JAY INC.
DATE: JUNE 11, 2023
PAGE 5 OF 5

NOT CONSTRUCTION DRAWINGS
DEPTH CONTOURS AND ORIENTATION TO
LAND FEATURES ARE APPROXIMATE



HALEY & ALDRICH, INC.
3131 Elliott Avenue,
Suite 600
Seattle, WA 98121
206.324.9530

CLIENT MEMORANDUM

1 September 2023
File No. 0202881-000

TO: D. Hittle & Associates, Inc.
Bob Schneider

FROM: Haley & Aldrich, Inc.
Mark R. Zablocki, P.E. (MA), Assistant Project Manager
Jeff S. Bruce, P.E., Project Manager

SUBJECT: Soil Conditions Memorandum
Hat Island Submarine Cable
Snohomish County, Washington

Haley & Aldrich, Inc. (Haley & Aldrich) presents this memorandum containing information on subsurface conditions for the proposed relocation of the Hat Island Submarine Cable at the two proposed site locations on Hat Island and the “Boneyard” site at the south end of the Port of Everett. This memorandum presents our current project understanding, and detailed subsurface exploration results. This work was performed in accordance with our proposal dated 30 August 2022 and your subsequent authorization.

Introduction

The Snohomish County Public Utilities Department (SnoPUD) is considering the replacement of an existing submarine cable, which provides power to Hat Island. The existing submarine cable spans the portion of Possession Sound between Hat Island and Mission Beach. Two locations have been identified for the launching and receiving of the new submarine cable. One location is in proximity to the existing cable landing on Hat Island, in an open area south of the Hat Island Marina. The other location is referred to as the “Boneyard”, which is located at the south end of the Port of Everett, west of Pigeon Creek Trail, and is currently being used to stage miscellaneous tooling and equipment.

The upland portion of the Hat Island site is relatively flat with an approximate ground surface elevation of elevation (El.) 20 feet. The shoreline at the site slopes west to east towards Possession Sound. The upland portion of the Boneyard site is relatively flat with an approximate ground surface elevation of El. 25. The shoreline at the site slopes east to west towards Possession Sound. The elevation datum used throughout this memorandum is the Mean Lower Low Water Datum (MLLW).

Subsurface Conditions

We subcontracted Holocene Drilling, Inc. of Puyallup, Washington, to conduct two test boring explorations under the technical observation of Haley & Aldrich. The test borings designated HC-1 (Hat Island) and HA22-1 (Boneyard) were advanced to depths of 76 and 80.4 feet below ground surface (bgs) respectively.

Our understanding of subsurface conditions was developed by evaluating soil conditions observed during the subsurface explorations, geotechnical laboratory testing, and information from a desktop study of geological conditions of potential replacement cable routes from Dick Sylwester¹. The nature and extent of variations between explorations at discrete locations may not be evident until construction. Appendices provide logs of our explorations (Appendix A), geotechnical laboratory test results (Appendix B), and a copy of Sylwester 2020 (Appendix C). Note: the cable alignment from Hat Island to the Boneyard site was evaluated as Route D within Sylwester 2020.

SOIL CONDITIONS

Test boring HC-1 at the Hat Island site encountered about 35 feet of medium dense beach and bluff deposits generally consisting of sand with variable silt and gravel over dense to very dense glacially overridden sand and silty sand deposits through the end of the boring at a 76-foot depth. Sylwester 2020 indicates offshore conditions by geophysical survey to be about 10 feet of unconsolidated material (bluff erosional deposits) over 30 feet of glaciomarine sediments, above dense glacially overridden soil. As the offshore bathymetry steepens, variable thickness of unconsolidated sediments were observed, likely from erosion and historical landslides. Conditions deeper offshore, on the relatively flat seabed, typically consisted of about 30 feet of marine sediments over glacially overridden material (Sylwester 2020).

Test boring HA22-1 at the Boneyard site encountered approximately 10 feet of loose to medium dense sand and gravel fill with variable amounts of silt, organics, and detritus, overlying a 12.5-foot-thick layer of dense sand with silt and gravel, beach and bluff deposits. The bottom of the beach and bluff deposits were observed to consist of a 4.5-foot thick layer of wood debris, between 18 and 22.5 feet bgs. Very dense to very stiff glacially overridden soils were encountered below the bottom of the wood debris layer and through the bottom of the test exploration to an 80.4-foot depth. The top 11.5 feet (22.5 to 34 feet bgs) of the glacially overridden soils consisted of a silty sand with gravel and scattered organics, glacial outwash soil. Below the glacial outwash from a 34-foot depth to the bottom of the boring at 80.4 feet, the soils were observed to be generally glacio-lacustrine soils consisting of interbedded layers of clays and silts, with various amounts of sand. Between depths of 59 to 68 feet, a very dense silty gravel layer with sand was encountered.

¹ Sylwester, R., 2020. *Desktop Study for Replacement of SNOFUD Hat Island Power Cable*. Richard Sylwester, 2020.

Based on our observations of our two borings and review of Sylwester 2020, we organized the project site into six engineering soil units (ESUs), as discussed below.

It is important to note that the subsurface conditions are quite variable and, given the nature of glacially consolidated and recessional materials, it should be assumed that zones of coarse grained material (cobbles and boulders) and zones of collapsible sands may be encountered along the route of the horizontal drilling.

- **ESU 1 – Historical Fill.** We observed approximately 10 feet of sand and gravel fill at the Boneyard site. The fill was observed to be loose to medium dense and contained organics and debris. No fill was observed on the Hat Island project site.
- **ESU 2 – Beach/Bluff Erosional Deposits.** The Hat Island and Boneyard project sites are generally underlain by beach and bluff erosional deposits. These beach and bluff erosional deposits are composed of medium dense to dense poorly graded sand to silty sand, deposited from wave action and erosion of the coastal cliffs and shoreline. We observed wood and shell debris in these deposits between depths of about 17 and 30 feet at the Hat Island site, and between 10 and 22.5 feet at the Port of Everett. Though not encountered in our borings, we note the potential for cobbles or boulders in this ESU due to the variable nature of erosional debris. Additionally, the relatively clean poorly graded sands encountered in the borings indicate the risk of collapse during horizontal directional drilling.
- **ESU 3 – Glacial Outwash.** Beneath ESU 2, we observed glacially overridden deposits (outwash deposits) composed of dense to very dense poorly graded sand to silty sand. This layer was not penetrated at the Hat Island site but was found to be 11.5 feet thick at the Boneyard site.
- **ESU 4 – Glaciolacustrine.** We encountered a fine-grained glacially overridden deposit at the Boneyard site at approximately 34 feet bgs. The strata consisted of approximate 5- to 10-foot-thick sections of either clay or silt, with varying amounts of sand with an increasing coarse fractions beyond a 60-foot depth. At the Boneyard site, a 9-foot-thick very dense silty gravel layer with sand was encountered within the glaciolacustrine soils.
- **ESU 5 – Glaciomarine Sediments.** Possibly up to 30 feet of glaciomarine sediments can be found beneath the eroded bluff deposits off both the Hat Island and Boneyard project sites. These sediments are documented in Sylwester 2020. Deposition of this material results as the floating remnants of glaciers continue to melt, releasing sediment caught in its structure that falls to the seafloor. These deposits are likely loose to medium dense and suspected to be liquefiable.
- **ESU 6 – Fine-Grained Marine Sediments.** The seabed is composed of fine-grained marine deposits deposited overtime and likely composed of silt and clay. These deposits rest above the glaciomarine sediments and glacially overridden deposits.

GROUNDWATER

At the time of drilling, we estimated the groundwater table to range from about 5 to 10 feet bgs on Hat Island and 10 to 15 feet bgs at the Port of Everett, based on observed moisture conditions of our drilling samples. Due to the nature of mud-rotary drilling, an exact groundwater elevation could not be observed at the time of drilling.

The groundwater table is anticipated to be tidally influenced and fluctuate with the high and low tides of the adjacent Puget Sound. The nearest National Oceanic and Atmospheric Administration (NOAA) station gauge (Station ID 9447130) is located in Seattle, Washington. Tidal information is available to the public on NOAA's website <<https://tidesandcurrents.noaa.gov/>>.

Conclusion/Limitations

This memorandum has been prepared for specific application to the proposed Hat Island cable crossing as described herein. Our comments are based in part upon data obtained from the referenced subsurface explorations and testing. The nature and extent of variations in subsurface conditions may not become evident until further explorations are conducted or until construction. If significant variations then appear, it may also be necessary to re-evaluate the conclusions and recommendations contained herein.

We appreciate the opportunity to provide services for this project and look forward to our continued association with you and the project team through completion of design and construction. Please contact us with any questions.

Enclosures:

Appendix A - Subsurface Exploration Logs

Appendix B - Geotechnical Laboratory Test Results

Appendix C - Report "Desktop Study for Replacement of SNOPUD Hat Island Power Cable"

\\haleyaldrich.com\share\sea_projects\Notebooks\1951600_Hat_Island_Submarine_Cable_Replacement\Deliverables\Memos\Soil Conditions Memo\2023_0901_HAI_HatIsland_SoilCond_F.docx

APPENDIX A
Subsurface Exploration Logs

KEY TO EXP LOGS (SOIL ONLY) - J:\GINTI.HC_LIBRARY.GLB - 2/12/20 12:17 - \\SEAF\PROJECTS\notebooks\1951600_HAT_ISLAND_SUBMARINE_CABLE_REPLACEMENT\FIELD DATA\PERM_GINT FILES\1951600-BL.GPJ - kz

Sample Description

Identification of soils in this report is based on visual field and laboratory observations which include density/consistency, moisture condition, grain size, and plasticity estimates and should not be construed to imply field nor laboratory testing unless presented herein. ASTM D 2488 visual-manual identification methods were used as a guide. Where laboratory testing confirmed visual-manual identifications, then ASTM D 2487 was used to classify the soils.

Relative Density/Consistency

Soil density/consistency in borings is related primarily to the standard penetration resistance (N). Soil density/consistency in test pits and probes is estimated based on visual observation and is presented parenthetically on the logs.

SAND or GRAVEL Relative Density	N (Blows/Foot)	SILT or CLAY Consistency	N (Blows/Foot)
Very loose	0 to 4	Very soft	0 to 1
Loose	5 to 10	Soft	2 to 4
Medium dense	11 to 30	Medium stiff	5 to 8
Dense	31 to 50	Stiff	9 to 15
Very dense	>50	Very stiff	16 to 30
		Hard	>30

Moisture

Dry	Absence of moisture, dusty, dry to the touch
Moist	Damp but no visible water
Wet	Visible free water, usually soil is below water table


USCS Soil Classification Chart (ASTM D 2487)

Major Divisions		Symbols		Typical Descriptions
		Graph	USCS	
Coarse Grained Soils More than 50% of Material Retained on No. 200 Sieve	Gravel and Gravelly Soils More than 50% of Coarse Fraction Retained on No. 4 Sieve		GW	Well-Graded Gravel; Well-Graded Gravel with Sand
			GP	Poorly Graded Gravel; Poorly Graded Gravel with Sand
			GW-GM	Well-Graded Gravel with Silt; Well-Graded Gravel with Silt and Sand
			GW-GC	Well-Graded Gravel with Clay; Well-Graded Gravel with Clay and Sand
			GP-GM	Poorly Graded Gravel with Silt; Poorly Graded Gravel with Silt and Sand
			GP-GC	Poorly Graded Gravel with Clay; Poorly Graded Gravel with Clay and Sand
	Sand and Sandy Soils More than 50% of Coarse Fraction Passing No. 4 Sieve		GM	Silty Gravel; Silty Gravel with Sand
			GC	Clayey Gravel; Clayey Gravel with Sand
			SW	Well-Graded Sand; Well-Graded Sand with Gravel
			SP	Poorly Graded Sand; Poorly Graded Sand with Gravel
Fine Grained Soils More than 50% of Material Passing No. 200 Sieve	Sands (5-12% fines)		SW-SM	Well-Graded Sand with Silt Well-Graded Sand with Silt and Gravel
			SW-SC	Well-Graded Sand with Clay; Well-Graded Sand with Clay and Gravel
			SP-SM	Poorly Graded Sand with Silt; Poorly Graded Sand with Silt and Gravel
	Silt (based on Atterberg Limits)		SP-SC	Poorly Graded Sand with Clay; Poorly Graded Sand with Clay and Gravel
			SM	Silty Sand; Silty Sand with Gravel
			SC	Clayey Sand; Clayey Sand with Gravel
Clays		ML	Silt; Silt with Sand or Gravel; Sandy or Gravelly Silt	
		MH	Elastic Silt; Elastic Silt with Sand or Gravel; Sandy or Gravelly Elastic Silt	
		CL-ML	Silty Clay; Silty Clay with Sand or Gravel; Gravelly or Sandy Silty Clay	
		CL	Lean Clay; Lean Clay with Sand or Gravel; Sandy or Gravelly Lean Clay	
Organics		CH	Fat Clay; Fat Clay with Sand or Gravel; Sandy or Gravelly Fat Clay	
		OL/OH	Organic Soil; Organic Soil with Sand or Gravel; Sandy or Gravelly Organic Soil	
Highly Organic (>50% organic material)		PT	Peat - Decomposing Vegetation - Fibrous to Amorphous Texture	

Minor Constituents

Minor Constituents	Estimated Percentage
Sand, Gravel	
Trace	<5
Few	5 - 15
Cobbles, Boulders	
Trace	<5
Few	5 - 10
Little	15 - 25
Some	30 - 45

Soil Test Symbols




CA	Chemical Analysis
CAUC	Consolidated Anisotropic Undrained Compression
CAUE	Consolidated Anisotropic Undrained Extension
CBR	California Bearing Ratio
CIDC	Consolidated Drained Isotropic Triaxial Compression
CIUC	Consolidated Isotropic Undrained Compression
CK0DC	Consolidated Drained k0 Triaxial Compression
CK0DSS	Consolidated k0 Undrained Direct Simple Shear
CK0UC	Consolidated k0 Undrained Compression
CK0UE	Consolidated k0 Undrained Extension
CRSCN	Constant Rate of Strain Consolidation
DS	Direct Shear
DSS	Direct Simple Shear
DT	In Situ Density
GS	Grain Size Classification
HYD	Hydrometer
ILCN	Incremental Load Consolidation
K0CN	k0 Consolidation
kc	Constant Head Permeability
kf	Falling Head Permeability
MD	Moisture Density Relationship
OC	Organic Content
OT	Tests by Others
P	Pressuremeter
PID	Photoionization Detector Reading
PP	Pocket Penetrometer
SG	Specific Gravity
TRS	Torsional Ring Shear
TV	Torvane
UC	Unconfined Compression
UUC	Unconsolidated Undrained Triaxial Compression
VS	Vane Shear
WC	Water Content (%)

Groundwater Indicators


	Groundwater Level on Date or At Time of Drilling (ATD)
	Groundwater Level on Date Measured in Piezometer
	Groundwater Seepage (Test Pits)

Sample Symbols

Well Symbols



Date Started: 02/10/2020 Date Completed: 02/10/2020 Drilling Contractor/Crew: Holocene Drilling, Inc. / Roddy
 Logged by: C. Kroskie Checked by: Z. Yell Drilling Method: Mud Rotary
 Location: Lat: 48.018713 Long: -122.321879 (WGS 84) Rig Model/Type: Diedrich D-120 / Truck-mounted drill rig
 Ground Surface Elevation: 12.00 feet (MLLW) Hammer Type: Auto-hammer
 Comments: Hat Island Hammer Weight (pounds): 140 Hammer Drop Height (inches): 30
 Measured Hammer Efficiency (%): Not Available
 Hole Diameter: Well Casing Diameter: NA
 Total Depth: 76 feet Depth to Groundwater: Not Identified



General Notes:

1. Refer to Figure A-1 for explanation of descriptions and symbols.
2. Material stratum lines are interpretive and actual changes may be gradual. Solid lines indicate distinct contacts and dashed lines indicate gradual or approximate contacts.
3. USCS designations are based on visual-manual identification (ASTM D 2488), unless otherwise supported by laboratory testing (ASTM D 2487).
4. Groundwater level, if indicated, is at time of drilling/excavation (ATD) or for date specified. Level may vary with time.
5. Location and ground surface elevations are approximate.




Project: Hat Island Submarine Cable Replacement
 Location: Everett, Washington
 Project No.: 0202881-000

Boring Log
 HC-1

Figure A-2
 Sheet 1 of 2

H:\BORING LOGS - HALEY\ALDRICH\COMBARESEA_DATA\GINTING\DC - HAT ISLAND SUBMARINE CABLE REPLACEMENT\FIELD DATA\BENT FILES\001000E_GPJ_1.mxd


Date Started: 02/10/2020 Date Completed: 02/10/2020 Drilling Contractor/Crew: Holocene Drilling, Inc. / Roddy
 Logged by: C. Kroskie Checked by: Z. Yell Drilling Method: Mud Rotary
 Location: Lat: 48.018713 Long: -122.321879 (WGS 84) Rig Model/Type: Diedrich D-120 / Truck-mounted drill rig
 Ground Surface Elevation: 12.00 feet (MLLW) Hammer Type: Auto-hammer
 Comments: Hat Island Hammer Weight (pounds): 140 Hammer Drop Height (inches): 30
 Measured Hammer Efficiency (%): Not Available
 Hole Diameter: _____ Well Casing Diameter: NA
 Total Depth: 76 feet Depth to Groundwater: Not Identified



General Notes:
 1. Refer to Figure A-1 for explanation of descriptions and symbols.
 2. Material stratum lines are interpretive and actual changes may be gradual. Solid lines indicate distinct contacts and dashed lines indicate gradual or approximate contacts.
 3. USCS designations are based on visual-manual identification (ASTM D 2488), unless otherwise supported by laboratory testing (ASTM D 2487).
 4. Groundwater level, if indicated, is at time of drilling/excavation (ATD) or for date specified. Level may vary with time.
 5. Location and ground surface elevations are approximate.

H:\BORING LOGS - HALEY\ALDRICH\COMSHARE\SEA_PROJECTS\NOTES\BOSONS\1000_HAT_ISLAND_SUBMARINE_CABLE_REPLACEMENT\FIELD DATA\BRL_GNT_FLIES\01101006_GPJ_1.tbl

Date Started: 09/12/2022 Date Completed: 09/12/2022 Drilling Contractor/Crew: Holocene Drilling, Inc.
 Logged by: Z. McIntire Checked by: M. Espinoza Drilling Method: Mud Rotary
 Location: Lat: 47.971234 Long: -122.229924 (WGS 84) Rig Model/Type: Diedrich D-70 Turbo / Track-mounted drill rig
 Ground Surface Elevation: 25.00 feet (MLLW) Hammer Type: Auto-hammer
 Comments: _____ Hammer Weight (pounds): 140 Hammer Drop Height (inches): 30
 Measured Hammer Efficiency (%): Not Available
 Hole Diameter: _____ Well Casing Diameter: NA
 Total Depth: 80.4 feet Depth to Groundwater: Not Identified



General Notes:

1. Refer to Figure A-1 for explanation of descriptions and symbols.
2. Material stratum lines are interpretive and actual changes may be gradual. Solid lines indicate distinct contacts and dashed lines indicate gradual or approximate contacts.
3. USCS designations are based on visual-manual identification (ASTM D 2488), unless otherwise supported by laboratory testing (ASTM D 2487).
4. Groundwater level, if indicated, is at time of drilling/excavation (ATD) or for date specified. Level may vary with time.
5. Location and ground surface elevations are approximate.




Project: Hat Island Submarine Cable Replacement
 Location: Everett, Washington
 Project No.: 0202881-000

Boring Log
HA22-1

Figure **A-3**
 Sheet **1 of 2**

HA SPRING LOG - HALEY ALDRICH COMB SHARE (SEA DATA) GINTIC INC. LIBRARY (GUL - 31823) 18-42 - HALEY ALDRICH COMB SHARE (SEA PROJECT) NOTES (BOOKS) (1000) LAT ISLAND SUBMARINE CABLE REPLACEMENT FIELD DATA (SERIAL GINT FILES) (01/10/08) GPJ - 10/06/11

Date Started: 09/12/2022 Date Completed: 09/12/2022 Drilling Contractor/Crew: Holocene Drilling, Inc.
 Logged by: Z. McIntire Checked by: M. Espinoza Drilling Method: Mud Rotary
 Location: Lat: 47.971234 Long: -122.229924 (WGS 84) Rig Model/Type: Diedrich D-70 Turbo / Track-mounted drill rig
 Ground Surface Elevation: 25.00 feet (MLLW) Hammer Type: Auto-hammer
 Comments: _____ Hammer Weight (pounds): 140 Hammer Drop Height (inches): 30
 Measured Hammer Efficiency (%): Not Available
 Hole Diameter: _____ Well Casing Diameter: NA
 Total Depth: 80.4 feet Depth to Groundwater: Not Identified



General Notes:
 1. Refer to Figure A-1 for explanation of descriptions and symbols.
 2. Material stratum lines are interpretive and actual changes may be gradual. Solid lines indicate distinct contacts and dashed lines indicate gradual or approximate contacts.
 3. USCS designations are based on visual-manual identification (ASTM D 2488), unless otherwise supported by laboratory testing (ASTM D 2487).
 4. Groundwater level, if indicated, is at time of drilling/excavation (ATD) or for date specified. Level may vary with time.
 5. Location and ground surface elevations are approximate.

APPENDIX B
Geotechnical Laboratory Test Results

SEATTLE - HC LAB SUMMARY (FOR REPORTS) - J:\GINT\HC_LIBRARY.GLB - 4/16/20 09:50 - L:\NOTEBOOKS\1951600 - HAT_ISLAND_SUBMARINE_CABLE_REPLACEMENT\FIELD_DATA\PERM_GINT FILES\1951600-BL.GPJ - hclab


Exploration	Sample ID	Depth	Gravel (%)	Sand (%)	Fines (%)	Liquid Limit	Plastic Limit	Water Content (%)	USCS Group Symbol	Soil Description
HC-1	S-1	5.0	37.8	54.0	8.3			7.2	SW-SM	WELL-GRADED SAND WITH SILT AND GRAVEL
HC-1	S-2	10.0	24.8	70.7	4.4			13.4	SW	WELL-GRADED SAND WITH GRAVEL
HC-1	S-3	17.0	39.7	56.9	3.5			11.2	SP	POORLY GRADED SAND WITH GRAVEL
HC-1	S-4	22.0						16.1		
HC-1	S-5	25.0								
HC-1	S-6	30.0	0.5	84.7	14.7			21.6	SM	SILTY SAND
HC-1	S-7	35.0								
HC-1	S-8	40.0	0.0	93.0	7.0			23.8	SP-SM	POORLY GRADED SAND WITH SILT
HC-1	S-9	45.0								
HC-1	S-10	50.0	0.0	87.2	12.8			22.0	SM	SILTY SAND
HC-1	S-11	55.0								
HC-1	S-12	60.0	0.0	91.3	8.7			18.5	SP-SM	POORLY GRADED SAND WITH SILT
HC-1	S-13	65.0								
HC-1	S-14	70.0						18.8		
HC-1	S-15	75.0								
HA22-1	S-1	2.5								
HA22-1	S-2	5.0								
HA22-1	S-3	7.5								
HA22-1	S-4	10.0	42.3	47.9	9.7			19.9	SP-SM	POORLY GRADED SAND WITH SILT AND GRAVEL
HA22-1	S-5	15.0								
HA22-1	S-6	20.0								
HA22-1	S-7	25.0	42.6	44.2	13.2			10.3	SM	SILTY SAND WITH GRAVEL
HA22-1	S-8a	30.0						7.8		
HA22-1	S-8b	30.9								
HA22-1	S-9	35.0						30.4		
HA22-1	S-10	40.0	5.9	21.0	73.2	28	17	16.8	CL	LEAN CLAY WITH SAND
HA22-1	S-11	45.0								
HA22-1	S-12	50.0						15.2		
HA22-1	S-13	55.0				26	17	15.7	CL	LEAN CLAY WITH SAND
HA22-1	S-14	57.5								
HA22-1	S-15	60.0	27.8	26.6	45.6			12.3	GC-GM	silty, clayey gravel with sand
HA22-1	S-16	62.5								
HA22-1	S-17	65.0				27	16	15.3	CL	LEAN CLAY WITH SAND
HA22-1	S-18	70.0						12.9		
HA22-1	S-19	75.0								
HA22-1	S-20	80.0						11.1		



Project: Hat Island Submarine Cable Replacement
 Location: Everett, Washington
 Project No.: 0202881-000

**Summary of
Laboratory Results**

Figure **B-1**
 Sheet **1 of 1**




HA:\ATTENBEG\LIMITS - C:\USERS\GARDNER\PHOTO\MICRO_LIBRARY\GLB - 1026201044 - \HALEVALDRICH\COMPARISON\PROJECTS\notes\BODS11061001_HAT_ISLAND_SUBMARINE_CABLE_REPLACEMENT\FIELD DATA\PERM_GINT FILES\99100006_GPI_1.mxd

Location and Description			LL	PL	PI	#200	MC%	USCS
● Source: HA22-1	Sample No.: S-10	Depth: 40.0 to 41.5						
LEAN CLAY WITH SAND			28	17	11	73	17	CL
■ Source: HA22-1	Sample No.: S-13	Depth: 55.0 to 56.5						
LEAN CLAY WITH SAND			26	17	9	NT	16	CL
▲ Source: HA22-1	Sample No.: S-17	Depth: 65.0 to 66.5						
LEAN CLAY WITH SAND			27	16	11	NT	15	CL

Remarks:

- AL performed on -#40 fraction
- AL performed on -#40 fraction
- ▲ AL performed on -#40 fraction

HC GRAIN SIZE - J:\GINT\HC_LIBRARY\GLB-4\16\20 09:49 - L:\NOTEBOOKS\1951600_HAT_ISLAND_SUBMARINE_CABLE_REPLACEMENT\FIELD_DATA\PERM_GINT_FILES\1951600-BL.GPJ - hclab



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	


Location and Description	% Cobbles	% Gravel	% Sand	% Silt	% Clay	MC%	USCS
● Source: HC-1 Sample No.: S-1 Depth: 5.0 to 6.5 WELL-GRADED SAND WITH SILT AND GRAVEL	0.0	37.8	54.0	8.3		7	SW-SM
■ Source: HC-1 Sample No.: S-2 Depth: 10.0 to 11.5 WELL-GRADED SAND WITH GRAVEL	0.0	24.8	70.7	4.4		13	SW
▲ Source: HC-1 Sample No.: S-3 Depth: 17.0 to 18.5 POORLY GRADED SAND WITH GRAVEL	0.0	39.7	56.9	3.5		11	SP
◆ Source: HC-1 Sample No.: S-6 Depth: 30.0 to 31.5 SILTY SAND	0.0	0.5	84.7	14.7		22	SM

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		13.152	3.976	1.685	0.439	0.243	0.110	0.44	36.28
■		7.758	1.579	0.816	0.463	0.289	0.233	0.58	6.77
▲		26.411	4.633	2.234	0.519	0.174	0.121	0.48	38.35
◆		0.981	0.330	0.222	0.121	0.076			

Remarks:

-
-
- ▲
- ◆

HC GRAIN SIZE - J:\GINT\HC_LIBRARY\GLB - 4/16/20 09:49 - L:\NOTEBOOKS\1951600_HAT_ISLAND_SUBMARINE_CABLE_REPLACEMENT\FIELD_DATA\PERM_GINT_FILES\1951600-BL.GPJ - hclab




COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Location and Description			% Cobbles	% Gravel	% Sand	% Silt	% Clay	MC%	USCS
●	Source: HC-1 Sample No.: S-8 Depth: 40.0 to 41.5 POORLY GRADED SAND WITH SILT		0.0	0.0	93.0	7.0	24	SP-SM	
■	Source: HC-1 Sample No.: S-10 Depth: 50.0 to 51.0 SILTY SAND		0.0	0.0	87.2	12.8	22	SM	
▲	Source: HC-1 Sample No.: S-12 Depth: 60.0 to 61.5 POORLY GRADED SAND WITH SILT		0.0	0.0	91.3	8.7	18	SP-SM	
◆	Source: HC-2 Sample No.: S-3 Depth: 15.0 to 16.5 SILTY SAND		0.0	0.0	67.6	32.4	27	SM	

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
●		0.414	0.310	0.276	0.191	0.117	0.089	1.33	3.50
■		0.243	0.189	0.171	0.123	0.080			
▲		0.693	0.439	0.375	0.275	0.160	0.089	1.93	4.91
◆		0.234	0.130	0.107					

Remarks:

-
-
- ▲ Sample S-3 from test boring HC-2 was from a previous study and is not a part of our subsurface understanding for either the Hat Island or Boneyard sites.
- ◆



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Location and Description	% Cobbles	% Gravel	% Sand	% Silt	% Clay	MC%	USCS
● Source: HA22-1 Sample No.: S-4 Depth: 10.0 to 11.5 POORLY GRADED SAND WITH SILT AND GRAVEL	0.0	42.3	47.9	9.7		20	SP-SM
■ Source: HA22-1 Sample No.: S-7 Depth: 25.0 to 26.5 SILTY SAND WITH GRAVEL	0.0	42.6	44.2	13.2		10	SM
▲ Source: HA22-1 Sample No.: S-10 Depth: 40.0 to 41.5 LEAN CLAY WITH SAND	0.0	5.9	21.0	73.2		17	CL
◆ Source: HA22-1 Sample No.: S-15 Depth: 60.0 to 61.5 SILTY, CLAYEY GRAVEL WITH SAND	0.0	27.8	26.6	28.0	17.6	12	GC-GM

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u	
●		15.906	5.435	2.689	0.589	0.161	0.079	0.81	69.03	
■		13.431	5.249	3.100	0.626	0.106				
▲	28	11	0.318							
◆			22.917	0.425	0.126	0.017	0.004	0.001	0.48	300.11

Remarks:

-
- Scattered wood debris
- ▲ AL performed on -#40 fraction
- ◆

HA GRAIN SIZE: C:\USERS\ING\ALDRICH\COMMS\SEA_PROJECTS\NOTED\0281931000_MTL_ISLAND_SUBMARINE_CABLE_REPLACEMENT\DATA\WENT_GINT_FILES\931000_RL_GPI_V066

APPENDIX C
Report “Desktop Study for Replacement of SNOPUD
Hat Island Power Cable”



DESKTOP STUDY FOR REPLACEMENT OF SNOPOD HAT ISLAND POWER CABLE

Prepared for: Snohomish County PUD
2012 California Avenue
Everett, Washington 98203
Contract No. CW2238251

Prepared by: Richard Sylwester
dicksylwester@gmail.com

Mr. Éric Schneider, Project Manager
Snohomish PUD
2012 California Avenue Everett, WA 98203

Reference: DESKTOP STUDY FOR REPLACEMENT OF SNOHUD TULALIP TO HAT (GEDNEY) ISLAND, POWER CABLE, SNOHOMISH COUNTY, WASHINGTON

Dear Mr. Schneider:

This desktop study provides preliminary information on the interpreted geologic and geophysical characteristics of seabed and sub-seabed conditions along an existing cable corridor. In addition, supplemental information is provided on three proposed alternative routes. The compiled information will be used by others to assist in selecting a route for a replacement power cable and for evaluating cable installation methods.

The existing corridor extends 2.5 nautical miles southwest from Mission Beach, located on the east shoreline of Possession Sound, to the northeast shoreline of Hat (Gedney) Island (Fig.1). The maximum water depth along this route is approximately 340 feet (Terrasond, 2019).




Figure 1. Location of existing power cable crossing

Sources for the geological and geophysical information presented in this document include: Washington State Department of Natural Resources (DNR) geologic information databases, Washington State Department of Ecology, the United States Geologic Survey office of Marine Geology data bases, the University of Washington Department of Oceanography, published

papers, reports from several geophysical investigations for pipeline and cable route studies in Puget Sound and a reconnaissance seismic reflection survey conducted for this study.

A. SUMMARY OF GEOLOGIC HISTORY




Figure 2. Thickness of continental glacier (m) over Puget Sound 16,000 years ago (Easterbrook, 1966).

The geologic history of the Puget Sound Lowlands (Puget Sound trough and marine waters adjacent rivers, valleys and islands) was predominated by continental glaciation (Bretz, 1913). Ice sheets and glaciers expanded south from Canada due to increased accumulation of snow and ice with an associated decrease in sea-level. Glacial advance and subsequent retreat occurred at least 4 times over the past 2 million years. The last advance and retreat (16,000 to 12,000 years before present) of the Cordilleran glacier was the Fraser glaciation that produced most of the present day geologic and topographic features (Thorson, 1980).

During the maximum advance ice thickness in Puget Sound was over 3,000 feet and there was a subsequent sea level lowering of 300 feet (Fig 2).

During the glacier advance, sediments composed of proglacial lake deposits (silt and clay), advance outwash material (sand and gravel) were deposited on older Pre-Vashon deposits. The older Pre-Vashon deposit are predominantly glacial and nonglacial sediments deposited during repeated glacial and interglacial periods during the past 2 million years.

As the Puget Lobe of the Vashon Stade glacier retreated northward, it deposited a discontinuous veneer of recessional outwash (sand and gravel) and local deposits of ablation till upon the glacial landscape. As the ice receded northward it thinned and begin to float on the waters flooding in from the Strait of Juan de Fuca resulting in glaciomarine drift being deposited offshore over earlier deposits of recessional outwash.

The geology of Whidbey and Camano Island and Mission Beach area south of Deception Pass area is glacial and interglacial. Along the shoreline the bluff deposits range from laminated silty clay to pebbly silt, stratified sand and gravel to well sorted sand and silt. The sea has been gradually eroding these coastal bluffs since the Vashon glacier began to melt. These sediments are now found on the wave cut benches (beaches) and cover the glacial sediment that underlie the offshore slopes.

Offshore, in deep-water, the seafloor is mantled with 10 to 30 feet of recent, fine-grained marine sediment overlain on glaciomarine and older glacial deposits that are thousands of feet thick in what is known as the Everett Basin (Barnett, 2010)

There is no evidence of bedrock outcrops on shore or in the reconnaissance seismic reflection data obtained for this investigation. However, Hat Island apparently has a bedrock core, the Fidalgo formation, that is an intrusive igneous mass characteristic of other rock formations on the San Juan Islands (McClellan, 1927). There is also evidence of exposed bedrock offshore on a seismic reflection profile obtained by the USGS that traversed from Possession Sound northward into Saratoga passing on the west side of Hat Island (Harding et.al., 1988).

B. POTENTIAL SUBMARINE GEOLOGIC HAZARDS

Several events and processes can occur that may have an adverse effect on the marine cable at the shore landings, on the adjacent offshore slopes and/or across the deep-water crossing. The following is a brief summary of these potential events.

Earthquakes: Earthquakes are the primary driver for most of the events and processes discussed below. Earthquakes may occur along any of the numerous faults found in Puget Sound as well as on the major Cascadia subduction zone located on the west coast of Washington. An earthquake associated with this subduction zone occurred approximately 300 years ago and is estimated to have produced a magnitude 9. Based on historical geologic investigation and related recent studies, the maximum recurrence interval for large ground-rupturing crustal-fault earthquakes in the Puget Lowland is about 400 to 600 years (Pratt, 1997).

Faults: Beneath the heavily populated Puget Sound region (Puget Lowland) is a regional complex of interrelated seismogenic (earthquake-causing) geologic faults (Fig. 3, Wikipedia). From north to south these include:

- Devils Mountain Fault
- Strawberry Point and Utsalady Point faults
- Mount Vernon/Woods Creek fault (Rogers Belt)
- Cherry Creek Fault Zone
- Southern Whidbey Island Fault (SWIF)
- Rattlesnake Mountain Fault Zone
- Seattle Fault
- Tacoma Fault
- Saddle Mountain Faults
- Olympia structure
- Doty Fault
- Saint Helens Zone and Western Rainier Zone




Figure 3. Puget Sound Faults.

Two fault zones are located relatively close to the cable crossing corridor. These are the South Whidbey Island Fault Zone (SWIF) and the Utsalady/Strawberry Fault Zone (UPF, SPF). The cumulative slip rate on the faults in this zone probably exceeds 0.5 mm/yr. and could be much larger (Fig. 4)

South Whidbey Island Fault Zone: SWIF is a broad, north-side-up fault zone (6–11 kilometers; 4–7 miles wide) dipping steeply to the northeast (Johnson 1996). The magnitude 7.4 earthquake modeled for the southern Whidbey Island fault zone is a shallow or crustal earthquake (Fig. 5). The black box shows the area of the modeled rupture and the intensity within the rupture zone varies from severe to violent (Intensity of VIII to IX).




Figure 4. Faults closest to cable.

Shallow quakes tend to be much more damaging than deep quakes of comparable magnitude (such as the M6.8 Nisqually earthquake in 2001). Excavations across several scarps near Woodinville revealed evidence of at least four earthquakes since deglaciation about 16,000 years ago, the most recent being less than 2,700 years ago.




Figure 5. Intensity along rupture of SWIF.

Utsalady Fault Zone

This fault (Fig. 6) is an oblique-slip and shows both horizontal and vertical slip as the crustal blocks are pressed together (Johnson 2004). Trenching on the UPF (at a scarp identified by LIDAR) shows at least one and probably two Holocene earthquakes of magnitude 6.7 or more. The most recent one occurred between AD 1550 to 1850 and was possibly triggered by the 1700 Cascadia Subduction Zone fault located off the Washington coast. These earthquakes probably produced tsunamis. Several nearby locations show evidence of tsunamis not correlated with other known earthquakes.




Figure 6. Utsalady fault zone and intensity for VII earthquake.

Landslides: Water saturation of loose sediments is the primary trigger of landslides in Puget Sound (Fig. 7). Other triggers can result from seismic events (earthquakes), deposition of eroded bluff sediments on the steep slopes, and rapid deposition of sediment offshore from flooding rivers. Slope failures in the loose, fine to medium-grained glaciomarine sediment occur as either retrogressive flow slides (RFS) or spontaneous liquefaction (SL). The RFS start in some area of the slope and develop retrogressively up slope. SL slides initiate at a point and spread in all direction, up and down slope at a very high rate.




Figure 7. Examples of landslides in Puget Sound (Walsh 2002).

Although steep slopes are very susceptible to landslides, old, deep-seated landslides may be reactivated, even where gradients are low. A change in slope of the terrain with an increased sediment loading, shocks and vibrations, change in water content, groundwater movement, and removing or changing the type of vegetation covering slopes are all contributing factors. In general, landslide hazard areas are where the land has characteristics that contribute to the risk of the downhill movement of material, such as the following:

- A slope greater than 40 percent
- A history of landslide activity or movement during the last 10,000 years
- Stream or wave activity, which has caused erosion, undercut a bank or cut into a bank to cause the surrounding land to be unstable
- The presence of an alluvial fan, indicating vulnerability to the flow of debris or sediments
- The presence of impermeable soils, such as silt or clay, which are mixed with granular soils such as sand and gravel.

Tsunamis: Large coastal and underwater landslides and seismic events may produce tsunamis, or tidal waves. These are a series of waves caused by the displacement of a large volume of water that moves away from the area of disturbance. This creates potential hazards in areas not located near the actual source of the wave. At least nine earthquake related tsunami deposits, dating back 2500 years, have been mapped in Washington with the youngest being from the 1700 A.D. Cascadia earthquake (Haugerud and Kelsey, 2017).

A landslide in 1820 at Camano Head generated a tsunami that inundated a fishing village on Hat Island (Shipmen, 2001). In addition to offshore landslides the collapses of river deltas have produced tsunamis. There are several potential sources for generating tsunamis in Puget Sound on river delta that are highly susceptible to seismic soil liquefaction and potentially prone to submarine landsliding and disintegrative flow failure (Fig. 8)




Figure 8. Areas of potential delta failures that may generate tsunamis or turbidity currents (Walsh 2002).

Liquefaction: This is a phenomenon in which earthquake shaking causes soils to rapidly lose their strength and behave like quicksand. This typically occurs in areas of loose, sandy,

saturated soils often found in low-lying coastal areas, underwater marine and riverine deposits, river deltas, artificial fills, and tidal flats. These areas of poorly consolidated soils tend to have a high liquefaction potential. For example, the liquefaction susceptibility of many river valleys and deltas—such as the land on either side of the Stillaguamish and Snohomish rivers is rated moderate to high (Fig. 8).

Turbidity Currents and Debris flow: Turbidity currents are sediment laden water that can result from the failure of sediment buildup on delta or steep slopes. They are high-density currents that have considerable scour and erosion capability. For example, in SE Alaska an earthquake triggered the collapse of a delta and the subsequent submarine landslide produced a turbidity current that flowed across a power cable resulting in failure of the cable (personal communication). The submarine delta was fed by a bedload dominated river, such as what occurs on the Snohomish River during heavy run-off.

Ship Traffic and Anchor Drag: Commercial seagoing vessel as well as fishing vessels may drop and drag an anchor in areas such as cable corridors, that are marked as exclusive zones. Since most of the planned cable is laid on the seabed, and not buried, it is susceptible to damage should such an anchor drop event occur.

The offshore area around Hat Island is in the Puget Sound Vessel Traffic Service Area (NOAA Chart 18443 which provides information to vessels regarding obstructions, cables, etc.


C. DISCUSSION OF CABLE CORRIDOR SEISMIC REFLECTION DATA

The following summarizes the results of the seismic reflection data obtained on a reconnaissance geophysical survey in the vicinity of the Hat Island and Mission Beach shore landings and along a single transect between the two landings. The seismic reflection data were obtained with a low-frequency (400 to 800 Hz), low power (60 joules, 120 db re 1 microbar at 1m) seismic reflection system and acquired on a digital acquisition system interfaced with GPS navigation (Sylwester, 1982).

Hat Island

Subbottom seismic reflection data were acquired on several parallel transects offshore of Hat Island (Fig. 9). Images of the subsurface reflection data for the three transects are presented below (Figs. 10, 11 and 12).

Figure 9. Location of transects for seismic reflection data.



The seabed in shallow water appears to be covered with approximately 10 feet of unconsolidated material obtained from bluff erosion and then reworked by wave action. The

divers report from the eel grass survey describes the seabed as sand and 0 to 4-inch rock from the shoreline to a depth of approximately 0 feet. From 0 to the -10-foot depth contour the seabed was predominantly sand and eel grass and sand between the -10- and -30-foot depth contour. This material overlays about 30 feet of glaciomarine deposits that rest on a thick sequence (in excess of 200 feet) of horizontally bedded glacial deposits. The slope is covered with unconsolidated sediment of variable thickness that shows hummocky surface expressions that are evidence of submarine slides (Line H1 and H2). A thick deposit of loose material truncates the underlying horizontally stratified glacial sediment (Line H3). Offshore in deep-water the seabed is mantled with approximately 30 feet of fine-grained, marine sediment overlain on glacial marine deposits.

The sequence shown in the three figures is most likely characteristic of the strata that would be observed on seismic data obtained along other areas of the eastern shoreline of Hat Island.




Figure 10. Examples of seismic reflection data on Line H1.




Figure 11. Examples of seismic reflection data on Line H2.




Figure 12. Examples of seismic reflection data on Line H3

Water well data: There is one well on Hat Island that is located between the marine ramp and the shoreline (Steve Stangvik personal communication). Ecology has it mapped offshore but describes the location to be on Port Susan Drive. This is where it is shown on the attached image but needs to be surveyed for an exact location. The borehole log describes 72 feet of fine to medium sand (Fig. 13).




Figure 13. Beach Well 1 on Hat Island.

Tulalip-Mission Beach

Subbottom seismic reflection data were acquired on a series of parallel transects offshore of Tulalip/Mission Beach (Fig. 14).




Figure 14. Location of transects for seismic reflection data shown in Figures 15, 16 and 17.

The subsurface reflection data on the three transect are all quite similar (Figs. 14, 15, 16) and have some similarity to the Hat Island seismic profiles. The seabed in the shallow water is covered with unconsolidated material from the beach that are bluff erosion deposits. These materials are continually transported downslope and on the seismic data show evidence of slumping and/or submarine landslides. The diver’s eelgrass report describes the presence of sand from the shoreline to a depth of -2 feet and mud from -2 feet to -30-foot water depth. Eel grass was mapped between the -2- and -6-foot depth contours. There is no evidence of the eel grass beds on the data due to the limited resolution of the seismic signal.

The unconsolidated beach and shelf sediments overlay about 30 feet of glaciomarine deposits that rest on a thick sequence (in excess of 200 feet) of horizontally stratified glacial deposits. Approximately 500 feet offshore the subsurface strata, particularly the horizontal glacial

deposits, can no longer be detected. The lack of subsurface penetration is most likely due to the presence of organic material laying on the seabed or within surficial fine-grained sediment. The degradations of organic debris generate gas (methane) that blocks the acoustic signal; quite common in many offshore areas in Puget Sound. However, it can be assumed that the horizontally stratified glacial deposits extend offshore to the slope and remain at the same relative depth.

Although the subsurface horizontal reflections cannot be detected beneath the areas that are acoustically opaque or blanked by the organic material, it is assumed that the slope is covered with a variable thickness of recent sediment, including slide material. Beneath these deposits are the horizontally stratified glacial deposits detected near shore and at the Hat Island landing as well. Offshore the seabed is mantled with at least 30 feet of fine-grained marine sediment.

There was no evidence on the seismic reflection data of the eel grass that was mapped near shore on the bathymetric survey (Fig. 14).




Figure 15. Example of seismic reflection data on Line M1.




Figure 16. Example of seismic reflection data on Line M2




Figure 17. Example of seismic reflection data on Line M3

Water Well Data (Fig. 18): One well was located close to where the existing cable lands on shore; approximately 400 feet eastward of the end the offshore geophysical survey transect (Well 1). A second well is located on Priest Point (Well 2). Elevations are not given for either well. Soils are sand, gravel and clay.




Figure 18. Water well 1 (ID 79775) and water well 2 (ID 79775)

<https://fortress.wa.gov/ecy/wellconstruction/map/WCLSWebMap/WellConstructionMapSearch.aspx>

Deep-water, Main Corridor Crossing

A single seismic reflection profile was obtained on a transect that ran approximately parallel to the existing cable route from Hat Island to Mission Beach. The subsurface stratigraphy was very uniform with approximately 30 feet of fine-grained marine sediment overlain on glacial marine deposits of unknown thickness (Fig. 19). Surface sediment samples obtained in deep-water by the Department of Ecology in the Port Gardner/Hat Island area classify the seabed sediment as a mixture of silt and clay (Port Gardner, 2014). Additional information on seafloor sediment is shown in several places on NOAA chart 18433.




Figure 19. Example of seismic reflection data near mid-channel

D. SUPPLEMENTAL GEOPHYSICAL SURVEYS

Two additional offshore surveys were conducted within the existing cable route by another contractors. The details and results of these investigations are presented in a separate report (Terrasond, 2019). Briefly summarized the geophysical methods and information obtained are as follow.

1. Bathymetric Survey: A multibeam bathymetric survey was conducted along a corridor centered on the existing cable route. The corridor was approximately 1200 feet wide and narrowed to 200 feet at each landing. Images of the bathymetric contours for Hat Island and Mission Beach, are presented below (Fig. 20). Not shown near Hat Island is a possible sunken barge located 450 feet north of the centerline (377,700N, 1,278,100E). It is quite apparent that the seafloor on the Hat Island landing is considerably more complex, with incised canyons and escarpments, compared to the gentle slope on Mission Beach. The entire profile shows that the seabed in deep-water (approximately 340 feet) is extremely flat. The locations of the existing power cable, mapped using a magnetometer and sidescan sonar, is near the as-built cable location (Figs. 20 and 21).




Figure 20. Bathymetry offshore Hat Island (left) and Mission Beach (Terrasond Ltd., 2019)




Figure 21. Bathymetry along cable route and location of existing cable (Terrasond Ltd, 2019).

2. Cable Survey: Data were acquired with a magnetometer and sidescan sonar to locate the actual position of the existing cable within the cable corridor. The sidescan sonar only detected the cable at the base of the slope near Hat Island. This suggests that the cable is buried in the soft sediment in deep-water and beneath landslide material on each slope. However, the magnetometer was able to detect several magnetic anomalies as the survey vessel traversed back and forth across the cable corridor. These magnetic anomalies are interpreted to indicate the presence of ferrous objects including the existing power cable and possibly crab pots or miscellaneous debris (Fig. 22).



Figure 22. Magnetometer and sidescan sonar data. White marks are location of magnetic anomalies Bathymetry along entire cable route and location of existing power cable based on interpreted magnetometer and sidescan sonar data (Terrasond Ltd., 2019).

E. ALTERNATE ROUTES

Four crossing routes are being evaluated for installation of the replacement marine cable to Hat Island (Fig. 23). These crossings originate at Mission Beach (A), the existing cable route, Camano Head (B), Whidbey Island (C), and Everett (D) and terminate at the appropriate location on Hat Island.




Figure 23. Proposed alternate routes to Hat Island.

Route A – Parallel to the existing marine power cable route, but slightly offset. This route runs from Mission Beach to an area just east of the Hat Island marina (Fig. 23).

Mission Beach and Mission Beach Heights Road above and below the bluff are extremely vulnerable to landslides based on field observations by the Tulalip Department of Community Development (Hazard Mitigation Plan 2010). Offshore there is evidence on the marine seismic reflection data, acquired during the reconnaissance survey, of several submarine landslides. On the Hat Island landing the slopes are quite steep particularly at the bottom of the slope where there appears to be an escarpment (Figure 20). Apparently, these conditions created no difficulty during installation of the existing cable nor resulted in failure where the cable passes over the escarpment. Based on the detailed bathymetric data it should be possible to select a route from shoreline to deep-water that would avoid the escarpment and areas of apparent submarine landslides.

Route B - extends from the southernmost tip of Camano Island (Camano Head), to the northeastern end of Hat Island (Fig. 23).

Previous recorded landslide at Camano Head suggests this is a very unstable slope. One failure produced a tsunami wave that inundated the north shore of Gedney Island. The presence of impermeable soils, such as silt or clay, which are mixed with granular soils such as sand and gravel are prone to failure when saturated (Fig. 24). Future landslides would potentially result in burial, suspension or separation of power cable.



There is also an obstruction, Fish Haven, located just southeast of Camano Head. This is mapped on NOAA Chart 18443.

Historical Note 1: People at Hat Island in the early summer morning (1820) saw Camano Island bluff smoking; they couldn't see it for the smoke; and there was something black coming toward them, and then they saw it was a wave. They fled to high land. Some the men and women, some of the children were drowned (Tweddell, 1953 p. 67)

Figure 24. Camano Head

Historical Note 2: Camano Island Head landslide and subsequent tsunami (1820). Interview of Indian tribe conducted by the U.S. Government in 1888. The extreme southern end of Camano Island collapsed and fell into the bay creating a huge tsunami that traveled across Gardner Bay destroying the Snohomish Indian village of Hibulb, located along the western shoreline of what is now Everett, Washington, It also buried an Indian encampment at the base of the collapsed bluff before continuing on and wiping out a seasonal fishing village on Hat Island. (Washington State History/Geology Shipman, 2001).

Water well logs: Several water wells are in the immediate area and the log from the deepest one was selected. All wells showed a sequence of interbedded silt, clay and sand. There was no elevation information on the well (Fig. 25). Soils are clay, sand and gravel.

MATERIAL	Steel Well	FROM	TO
Top Soil		0	3
GRAY CLAY		3	79
GRAY SANDY CLAY		79	163
GRAY CLAY & GRAVEL		163	227
BROWN SANDY CLAY		227	255
GRAVEL & SAND		255	302
BROWN CLAY		302	324
BROWN SANDY CLAY		324	358
GRAY SAND & GRAVEL		358	365
358 - 365 WAS SALT WATER			
PULLED BACK 20' CASING &			
DRILLED WITH 6 SACKS OF			
CEMENTITE - PERFORATED UPPER			
ZONE -			




Figure 25. Water well data at Camano Head. Steel Well (ID 83500).

<https://fortress.wa.gov/ecy/wellconstruction/map/WCLWebMap/WellConstructionMapSearch.aspx>

Route C - extends from the eastern shore of Whidbey Island to the northwestern tip of Hat Island (Fig. 23).

At this landing impermeable soils, silt or clay, are mixed with granular soils including sand and gravel. This combination is highly prone to failure particularly on the heavily forested, steep slopes. Large trees leaning downslope are evidence of active slope movement and may result in a catastrophic slope failure such as is evident in the right hand image below (Fig. 26).



Figure 26. East shoreline of Whidbey Island showing Alt Route C and landslide

The water wells are located on top of the bluff and show that the soils are predominantly silty sand and clay (Figure 27)



MATERIAL	FROM	TO
Reddish Brown Soil	0	2'
Brown Sandy Gravel	2'	30'
Gray Sand	30'	58'
Brownish Gray Sand	58'	62'
Greenish Silty Sand	62'	68'
Gray Sandy Clay	68'	105'
Gray Clay	105'	128'
Gray Sand (w/water)	128'	142'
Gray Clay	142'	

Figure 27. Water well, Whidbey 1870403

<https://fortress.wa.gov/ecy/wellconstruction/map/WCLSWebMap/WellConstructionMapSearch.aspx>

There are several potential problems with this route.

On the westside of Hat Island, in Saratoga Passage, a USGS geophysical seismic survey mapped a bedrock intrusion which must be associated with the igneous intrusive rock forming the core of Hat Island (Harding 1988, McClellan, 1927). This rock obstruction and rock debris

on the seabed would require a detailed survey to map a safe and unobstructed route through the area (Fig 28).




Figure 28. Location of seismic image

Located in Saratoga Passage, approximately 6500 feet west of Hat Island is a 1000-foot-wide cable corridor that runs north-south. This may contain a fiberoptic communications cable and a potential conflict with a power cable (NOAA Chart 18445).

There are documented landslides on western shore of Camano in Saratoga Passage (Whiteaker, 2008) and at the southernmost tip of Camano. These have the potential for producing tsunami wave and turbidity currents on the seabed that could part or bury the cable.

Route D - extends from the Port of Everett to the easternmost tip of Hat Island (Figure 23).

Snohomish River during flooding transports large concentrations of logs and debris. This debris if discharged into Possession Sound could impact the marine power cable.

Turbidity currents may be produced by Snohomish River and/or failure of the delta front. This area was impacted by tsunami wave that generated by 1820 Camano Head landslide.

Historical Note: Exposed channel banks along distributaries of the lower Snohomish delta reveal evidence of at least three episodes of liquefaction, one event of abrupt subsidence and at least one tsunami during the past 1200 years (Bourgeois, 2001).


F. CLOSING

This work was performed in accordance under Professional Services Contract No. CW2238251 agreement between SNOPOD and Richard Sylwester. I trust this letter report meets your needs and ask that you contact me with any questions or comments on the content.

Sincerely

Richard Sylwester

Richard Sylwester L.E.G., L.G.
Senior Marine Geophysicist
Northwest Geophysical Services



APPENDIX: BIBLIOGRAPHY AND REFERENCES

- Barnett, E.A., R.A. Haugerud, B.L. Sherod, C.S. Weaver, T.L. Pratt and R.J. Blakely, Preliminary atlas of active shallow tectonic deformation in the Puget Lowland, Washington: USGS Open File Report 2010-1149.
- Booth, D. B., 1994, Glaciofluvial infilling and sour of the Puget Lowland, Washington, during ice-sheet glaciation: *Geology*, v. 22, p. 695-698.
- Bourgeois, J. and S.Y. Johnson, 2008, Geologic evidence of earthquakes at the Snohomish Delta, Washington, in the past 1200 years: *Geo. Soc. Amer. Bull* 113: 482-494.
- Bretz, J. H., 1913, Glaciation of the Puget Sound regions: Washington Geological Survey Bulletin No. 8, 244 p.
- Dethier, D.J., Pessel, F., Keuler, R. Dalzarini, M and Pevear, D., 1995, Late Wisconsinian glaciomarine deposition and isostatic rebound, northern Puget Lowland, Washington, *GSA: Bulletin*, v. 74, p 1465-1483.
- Findley, D., 2001, Overview of Puget Lowland geology; A training course for Golder Associates, Redmond, WA.
- Easterbrook, D.J. 1966, Glaciomarine environments and the Fraser glaciation in northwest Washington, Guidebook for First Pacific Coast Friends of the Pleistocene Field Conference, 52.
- Hampton, M.S., H.J. Lee and J. Locate, 1996, Submarine landslides: *Rev. Geophys.* 34: 33-59.
- Harding, S.T., T.P. Barnhard, and T.C. Urban, 1988. Preliminary data from the Puget Sound multichannel seismic-reflection survey. USGS Open-File Report 88-698.
- Haugerud, R.A. and H.M. Kelsey; 2017, From the Puget Lowland to east of the Cascade Range; geologic excursion in the Pacific Northwest: *GSR Field Guide* 49.
- Johnson, S.Y., C.J. Potter, J.M. Armentrout. 1996, The southern Whidbey Island Fault; an active structure in the Puget Lowland, Washington: *Geological Society of America Bulletin* 108: 334-354.
- Johnson, S.Y., S.V. Dadismn, D.C. Mosher, R.J. Blakely and J.R. Child, 2010, Active tectonics of the Devils Mountain Fault and related structures, Northern Puget Lowland and Eastern Strait of Juan de Fuca Region: *Pacific Northwest Professional Geological Survey of Canada*, Paper 1643.
- Johnson, S.Y., A.R. Nelson, S.F. Personius, R.E. Wells, 2004, Evidence for late Holocene earthquakes on the Utsalady Point fault, northern Puget Lowland, Washington: *Bull Seis. Soc. Amer.* 94: 2299-2316.

McLellan, Roy, Davidson, 1927, The Geology of the San Juan Islands, University of Washington Publications in Geology.

NOAA OAR Special Report Puget Sound Tsunami Sources—2002 Workshop Report A contribution to the Inundation Mapping Project of the U.S. National Tsunami Hazard Mitigation Program.

Palmer, S.P., September 2004, Liquefaction susceptibility map of Snohomish County, Washington, DNR.

Port Gardner Bay Regional Background Sediment Characterization: Final Data Evaluation and Summary Report; Publication 14-09-339, 2014.

Pratt, Thomas L., S. Johnson, C. Potter, 1997, Seismic reflection images beneath Puget Sound, western Washington State: The Puget Lowland thrust sheet hypothesis; Journal of Geophysical Research vol. 102, B12, Dec 10, 1997.

Shipman, Hugh, 2001, The Fall of Camano Head: A Snohomish account of a large landslide and tsunami in Possession Sound during the early 1800s: TsunInfo Alert, v.3, No. 6, p13-14.

Sylwester, R.E., and M.L. Holmes, 1987, Marine geophysical evidence of a recent submarine slope failure in Puget Sound Washington: Proceedings, Oceans 89, 5: 1524-1529.

Sylwester, R.E. 1982, Single-channel, high-resolution seismic-reflection profiling: A review of the fundamentals and instrumentation: Geophysical Exploration at Sea, CRC Press, Boca Raton, FL.

Sylwester, R.E., L.C. Bennett, M.A. Sheriff and R.C. Bostrom, 1971, The determination of active fault zones in Puget Sound Washington by means of continuous seismic profiling, in Proceedings: The Int. Symp. On the engineering properties of sea-floor soils and their geophysical identification; National Science Foundation; Seattle, WA 1971.

Terrasond Ltd, 2019, Hat Island to Tulalip Cable Corridor Multibeam Bathymetry.

The Geology of the San Juan Island (Igneous Rocks) www.nps.gov/parkhistory

Walsh, T.J., Other Tsunami sources in Washington, Department of Natural Resources.

Washington State History/Geology March 29, 2017

Whiteaker, William, 2008, Landslide generated tsunamis: A smoking gun in Saratoga Passage, Puget Sound, Washington: Oceanography 499 Senior Thesis, School of Oceanography, Univ. of Washington.

Wikipedia-Puget Sound Faults

https://earthquake.usgs.gov/scenarios/eventpage/bssc2014573_m6p69_se/executive

<https://fortress.wa.gov/ecy/wellconstruction/map/WCLSWebMap>


<https://ecology.wa.gov/Water-Shorelines/Water-supply/Wells>

<https://fortress.wa.gov/ecy/publications/SummaryPages/1409339>

<https://www.dnr.wa.gov/geologyportal>

https://www.nps.gov/parkhistory/online_books/geology/publications/state/wa/uw-1927-2/sec4.htm

<https://www.nps.gov/parkhistory>



DRAFT

Hat Island Multibeam Bathymetric Survey Report



Prepared for



Public Utility District No. 1 of Snohomish County




Submitted by:



Tetra Tech, Inc.
19803 North Creek Parkway
Bothell, WA 98011

September 9, 2022



CONTENTS

- 1. Introduction.....1**
- 2. Technical Approach.....2**
 - 2.1 Primary and Alternative Cable Routes..... 2
 - 2.2 Bathymetric Survey 2
 - 2.3 Survey Equipment 2
 - 2.4 Survey Vessels..... 2
 - 2.5 Geodesy..... 3
 - 2.6 Survey Control and Validation 4
 - 2.6.1 MBE Patch Test 6
 - 2.6.2 Quality Control Procedures..... 6
 - 2.6.3 Sound Speed Casts 7
 - 2.6.4 Data Processing 7
- 3. Data Deliverables.....10**
- 4. Data Discussion 11**
 - 4.1 General Morphology 11
 - 4.1.1 Hat Island Landing..... 13
 - 4.1.2 Everett Primary Landing 14
 - 4.1.3 Everett Alternative Landing15
 - 4.2 Features of Interest..... 15
 - 4.2.1 Features and Potentially Anthropogenic Objects 15
 - 4.2.2 Sea Grasses 17

LIST OF TABLES

- Table 2-1. Survey Equipment..... 2
- Table 2-2. Survey Geodesy 3
- Table 2-3. Survey Control Points..... 5
- Table 2-4. GNSS QC Results..... 5
- Table 2-5. R/V David Humes Sensor Offsets (in feet)..... 6
- Table 2-6. MBE Patch Test Calibration Results for 08/11/2022 and 08/15/2022 6
- Table 2-7. R/V David Humes Bar Check Results..... 7
- Table 4-1. Features Observed in Bathymetric Data 16

LIST OF FIGURES

Figure 1-1.	Hat Island to Port of Everett Preliminary Cable Route Including alternative landing at Harborview Park.....	1
Figure 2-1.	Tetra Tech Survey Vessel with R2Sonic 2026 MBE on Starboard Stern.....	3
Figure 2-2.	NAVD-88 to MLLW Conversion used for Deliverables.....	4
Figure 2-3.	Survey Control Established at the Port of Everett by the District.....	4
Figure 2-4.	Photos of the District’s Survey Control on Port of Everett Property	5
Figure 2-5.	Everett Landing North – IHO Special Order Compliance Test.....	8
Figure 2-6.	Everett Landing South – IHO Special Order Compliance Test.....	8
Figure 2-7.	Hat Island Landing – IHO Special Order Compliance Test.....	9
Figure 2-8.	Cable Route Deep Water – IHO Order 1a Compliance Test.....	9
Figure 2-9.	Data Comparison between Tetra Tech Data Recorded in this Survey, and an Overlapping Survey Area from 2017	10
Figure 4-1.	Seabed descends steeply and route crosses the tow of a turbidity flow.....	12
Figure 4-2.	Cross-sectional profile through an area of side slopes.....	12
Figure 4-3.	Hat Island Landing Bathymetry	13
Figure 4-4.	Approach to Everett Primary Landing	14
Figure 4-5.	Slope to Everett Primary Landing.....	15
Figure 4-6.	Alternate Everett Landing Object 1.....	16
Figure 4-7.	Primary Everett Landing Seabed Scars	16
Figure 4-8.	Linear Seabed Scars Near Hat Island.....	17

LIST OF APPENDICES

- APPENDIX A: ASCII FORMAT GRIDDED BATHYMETRY OF THE MULTIBEAM DATA
- APPENDIX B: SHP FILES OF CONTOURS AT 5 AND 10FT ELEVATION INTERVALS
- APPENDIX C: CHARTS SHOWING THE SURVEY CORRIDOR, HILLSHADE DEM SURFACE, ELEVATION CONTOURS AND SLOPE

1. INTRODUCTION

Public Utility District No. 1 of Snohomish County (District) issued professional services contract CW2248694 Hat Island Multibeam Echosounder (MBE) Bathymetric Survey to Tetra Tech on August 1, 2022 and notice to proceed on August 2, 2022. The bathymetric survey is needed to support planning and route siting for a replacement of the existing power supply cable.

The District provides electrical service to Hat Island, also known as Gedney Island located near Everett, WA, via a 45-year old submarine power distribution cable. The existing 3-phase cable was installed in 1974. The 12kV electrical distribution cable extends from Mission Beach (west of Marysville, WA, on the Tulalip reservation) to Hat Island, a distance of approximately 16,000 feet. The District serves Hat Island from Tulalip substation, circuit 12-507. The District provides service to approximately 250 residential and business customers on Hat Island, and its population fluctuates seasonally. The island's electric service also powers its drinking water system. The existing submarine cable is nearing the end of its serviceable life and is at risk of failure. To avoid a potential emergency situation which would isolate the residents of Hat Island from electric service, the District plans to install a new 3-phase electric submarine cable along a route from Everett to Hat Island (Fig. 1).

To continue reliable service to District customers, the existing cable will remain energized while the new line is installed. The new cable will be installed from the shoreline in Everett to Hat Island. The shore ends at both landings will be installed via horizontal directional drilling (HDD) to avoid the sensitive nearshore environment and surface laid between the HDD punchouts at each landing.

This report summarizes the bathymetric survey effort, data acquired and the project deliverables. The deliverables include an updated digital terrain model (DTM) along the survey routes to assist the District with planning a follow on geophysical survey and to inform the future cable replacement and installation efforts.




Figure 1-1. Hat Island to Port of Everett Preliminary Cable Route Including alternate landing at Harborview Park

The survey scope of work included:

1. Develop a detailed bathymetric map at both shore landings and along the cable route as follows:
 - a. Map areas containing seagrass(es), <40m water depth (WD) to ≥ 15 m WD, at the landing sites;
 - b. Identify areas of active or potential submarine landslides and/or mobile sediments (i.e. sand waves) at each landing (<40m WD to ≥ 15 m WD); and
2. Data processing, reporting and charting

2. TECHNICAL APPROACH

2.1 Primary and Alternative Cable Routes

Following noticed to proceed the District provided Tetra Tech with the primary and alternative routes in a format exported from Navionics software. Tetra Tech reviewed the routes and available existing data and proposed a survey plan based on District input and requirements.

2.2 Bathymetric Survey

A high-resolution MBE bathymetric survey was conducted between August 8 and September 15, 2022. The survey equipment, control and methods are summarized in the following Sections.

2.3 Survey Equipment

The equipment used to complete the survey efforts is summarized in Table 2-1.

Table 2-1. Survey Equipment

Equipment	System(s)	Details
Multibeam Echosounder	R2Sonic 2026	90/170-455 kilohertz (kHz) (selectable) 0.45 x 0.45° beamwidth and TruePix enabled
Heading and Motion Reference System	SBG Ekinox 2-D	Pitch, roll, and heading (yaw) accuracy of <0.02°. Heave accuracy of 5 centimeters or 5%, whichever is greater for period of 20 seconds or less.
Sound Velocity Profiler	YSI Castaway CTD	Conductivity, temperature, depth, and sound velocity
Sound Speed Sensor for MBE	Valeport, MiniSVS	Direct velocity measurement

2.4 Survey Vessels

The 24-foot survey vessel, R/V David Humes shown in Figure 2-1, was mobilized to Everett, WA and calibrations, including a multibeam patch test, were completed before commencing the bathymetric survey.



Figure 2-1. Tetra Tech Survey Vessel with R2Sonic 2026 MBE on Starboard Stern

2.5 Geodesy

Horizontal (X, Y) positioning data for the project were collected in North American Datum 1983 (2011 Adjustment (NAD83[2011])), State Plane Washington North. Elevation data (Z) were collected in North American Vertical Datum 1988 (NAVD-88) using Geoid18 and converted into Mean Lower Low Water (MLLW) heights using a conversion provided by the District (Table 2-2 and Figure 2-1). Distance and depth information were recorded in and provided digitally and on charts in U.S. Survey Feet.

Table 2-2. Survey Geodesy

Parameter	Setting
Projection	State Plane
Zone	Washington North (FIPS 4601)
Horizontal Datum	NAD83 (2011)
Vertical Datum	NAVD88 (Geoid18) and MLLW 1983 - 2001
Distance Unit	U.S. Survey Feet
Depth Unit	U.S. Survey Feet
Geoid Model	2018-CONUS

DATUM AND TIDAL INFORMATION

1. BASIS OF BEARINGS FOR THIS PROJECT IS GRID NORTH, WASHINGTON COORDINATE SYSTEM NORTH ZONE NAD 83 (2011): BASED ON GLOBAL NAVIGATION SATELLITE SYSTEM (GNSS) OBSERVATIONS.
2. VERTICAL DATUM IS MEAN LOWER LOW WATER (MLLW), NOAA STATION 9447773 TULALIP BAY EPOCH 1983-2001. TIDAL DATUMS AND SUBSEQUENT CONVERSIONS ARE AS FOLLOWS:

DATUM	ELEVATION
MEAN LOWER LOW WATER (MLLW)	0.00
NAVD88	2.04
MEAN LOW WATER (MLW)	2.78
MEAN HIGH WATER (MHW)	10.22
MEAN HIGHER HIGH WATER (MHHW)	11.06

3. EXTREME LOW TIDE (ELT) AS SHOWN HEREON, AND AS DEFINED BY PUBLISHED DNR GUIDANCE MEANS THE LINE AS ESTIMATED BY THE FEDERAL GOVERNMENT BELOW WHICH IT MIGHT REASONABLY BE EXPECTED THAT THE TIDE WOULD NOT EBB. IN THE PUGET SOUND AREA OF WASHINGTON STATE, THIS LINE IS ESTIMATED BY THE FEDERAL GOVERNMENT TO BE A POINT IN ELEVATION 4.50 FEET (PLUS OR MINUS 0.5 FEET) BELOW THE DATUM PLANE OF MEAN LOWER LOW WATER, (0.0).

Figure 2-2. NAVD-88 to MLLW Conversion used for Deliverables

2.6 Survey Control and Validation

Vertical and horizontal positioning was achieved using a high-accuracy global navigation satellite system (GNSS) system with real-time kinematic (RTK) corrections from the Washington State Reference Network (WSRN) utilizing a single station/mount point. Corrections were received via cellular data network from station “CBLV.”

Prior to mobilizing for the bathymetric survey Tetra Tech coordinated with the District’s survey department manager (Michael Lynch) who established control on Port of Everett Property as shown in Figure 2-3 and Figure 2-4. The control information is provided in Table 2-3.



Figure 2-3. Survey Control Established at the Port of Everett by the District



Figure 2-4. Photos of the District’s Survey Control on Port of Everett Property (rebar w/ yellow cap photo on left used for RTK and mag nail in asphalt photo on right)

Table 2-3. Survey Control Points

Control Points (Boneyard POE)	Northing	Easting	Elev. (NAVD88)
Rebar w/Yellow Cap (Base)	357395.034	1298303.786	18.84
Mag Nail in Asphalt (QC)	357472.423	1298464.931	18.15

Each day of the survey effort the Mag Nail QC point was occupied with the rover GNSS and the measured position compared to the recorded position shown in Table 2-3. The offsets between the measured and recorded positions are provided in Table 2-4. These QC efforts documented that the GNSS system provided positional accuracy of better than 0.1 feet which was within positioning tolerance for the system and survey effort.

Table 2-4. GNSS QC Results

Trimble R10 Rover RTK QC	Northing (feet)	Easting (feet)	Elevation (feet)	Delta North	Delta East	Delta Elev.
220805 QC Mag	357472.394	1298464.908	18.174	-0.029	-0.023	0.024
2220811 QC Mag	357472.407	1298464.910	18.133	-0.016	-0.021	-0.017
2220812a QC Mag	357472.395	1298464.939	18.099	-0.028	0.008	-0.051
22220815 QC Mag	357472.362	1298464.939	18.147	-0.061	0.008	-0.003

Throughout the survey, sound velocity profiles were collected and applied to the MBE data to correct for any variations in sound velocity in the water column.

An inertial measurement unit (IMU) was used to define the origin and orientation of the X, Y, and Z axes of the vessel's local reference frame. Table -5 provides the offsets, measured in feet, used for the QINSY hydrographic survey software, hardware setup. These measurements were also utilized in the Qimera, hydrographic data processing software, Vessel Configuration File (VCF) during processing of the multibeam data.

Table 2-5. R/V David Humes Sensor Offsets (in feet)

Sensor	Across (Starboard Positive)	Along (Forward Positive)	Vertical (Down Negative)
R2Sonic 2026 Tx	1.242	1.477	-4.375
Motion Sensor / Navigation (Ekinox 2-D)	0.00	0.00	-0.246

2.6.1 MBE Patch Test

A standard MBE patch test, also known as an installation calibration test, was carried out to calculate the angular offsets between the MBE and the motion reference unit (MRU). The installation calibration process is used to derive the roll, pitch, and yaw angular offsets between the multibeam sonar and the local reference frame defined by the MRU's IMU. The installation calibration tests are also used to determine latency in the positioning equipment. The sonar, positioning system, and data collection computer are all time-synchronized to GPS Coordinated Universal Time (UTC), which should result in a zero-position latency (Table 2-6.6). The sonar mount was reconfigured on 11 and 15 August, which required patch tests.

Table 2-6. MBE Patch Test Calibration Results for 08/11/2022 and 08/15/2022

Device	Date	Latency	Roll	Pitch	Yaw
R2Sonic 2026	11-August	0.00	2.487	0.188	-0.296
R2Sonic 2026	15-August	0.00	2.386	0.019	1.242

2.6.2 Quality Control Procedures

Quality control procedures were performed to confirm the vessel draft as well as the measured ellipsoidal height of the R/V *David Humes*' Center of Gravity (COG). This procedure was conducted by taking consecutive RTK shots at the waterline with a Trimble R10 Rover while simultaneously recording the vessel's waterline elevation display by the data acquisition software (Qinsy) on the R/V *David Humes*.

A test referred to as a "bar check" was conducted to verify the operation and accuracy of the multibeam sonar. A reflective target was suspended at a known depth below the sonar head and a depth measurement was taken using the survey software, correcting for the measured distance to the acoustic center of the sonar below the water surface. The sonar depth was determined by measuring

the depth of a defined point on the sonar mount, then adding the known vertical offset between the mount point position and the sonar acoustic center. This offset was then added to the depth reported by the sonar and compared to the depth of the acoustic target. The bar checks verified the sonar was accurately measuring depths.

Table 2-7. R/V David Humes Bar Check Results

Date	QINSy Measured Depth	Mount Point Draft	Mount Point to Acoustic Center Offset	Total Draft (feet)	Bar Depth (feet)	Delta
12-Aug	7.1	2.462	0.476	10.038	10	0.038
15-Aug	7.7	1.806	0.476	9.982	10	-0.018

2.6.3 Sound Speed Casts

Changes in sound speed through the water column affect the MBE's individual beams in both the angle and distance calculated from the propagation times. To compensate for these effects, data processing must model the effects as a function of beam launch angle and time. To implement these calculations, sound speed profiles were recorded through the water column using conductivity, temperature, depth (CTD) sensors from which sound speeds versus depths are derived. Sound velocity casts were performed at the start and end of data collection each day and taken as needed throughout the day using a handheld CastAway-CTD device.

2.6.4 Data Processing

A SBG Ekinox 2-D inertial navigation system with RTK corrections from the WSRN, station PFLD, were used for real time horizontal and vertical positioning of the survey data. Following the survey, the real-time inertial navigation data were post-processed using the base station RINEX files to improve accuracy using SBG Q inertia software. The post processed positioning and attitude solution was applied to the data in Qimera and the sounding data was then filtered and reviewed to remove clearly erroneous soundings.

Accuracy and precision are a function of the positioning and attitude measurements errors, timing errors, water depth, and water sound speed profile. To confirm accuracy and precision Tetra Tech performed additional QC measures after the data was post processed. This method compares the final surface to a processed data cross line that provides a statistical analysis to confirm the effort met or exceeded project specifications. A Qimera processing software tool that evaluates compliance with International Hydrographic Organization (IHO) standards was used to verify the accuracy of the data products. This tool compares MBE cross line data with survey main line data. Separate checks were conducted at each of the landings and in one of the deepest areas of the survey. The landing areas (<40 m deep) were evaluated for compliance with the IHO Special Order specifications, and the deep area (>40 m deep) was evaluated relative to IHO Order 1a specifications. These checks verified that IHO Special Order specifications and IHO Order 1a specifications were achieved in the shallow and deepwater, respectively. Figures 2-2 through 2-5 provide the results for the four areas in both tabular and graphic format.

An additional check for errors was performed with a comparison between the bathymetry surface, delivered with this report, and soundings from the NOAA S-57 charts covering the survey area. Survey data near the landing areas typically matched the chart soundings to within 0.1 to 0.2 feet. More variability was observed in the deepest (>400ft) areas of the survey, however all comparisons were within the IHO Order 1a specification limit.

Statistic	Value
Special Order Error Limit	1.21815
Special Order # Rejected	1078
Special Order P-Statistic	0.00737881
Special Order Test	ACCEPTED
Number Of Points	146094
Grid Cell Size	3.280
Difference Mean	-0.430
Difference Median	-0.424
Difference Std. Dev	0.241
Difference Range	[-2.197, 1.698]
Mean + 2*Stddev	0.912
Median + 2*Stddev	0.907
Data Mean	-159.393
Reference Mean	-158.963
Data Z-Range	[-282.045, -87.981]
Reference Z-Range	[-281.739, -87.662]

Figure 2-5. Everett Landing North – IHO Special Order Compliance Test

Statistic	Value
Special Order Error Limit	0.524719
Special Order # Rejected	8021
Special Order P-Statistic	0.00820703
Special Order Test	ACCEPTED
Number Of Points	977333
Grid Cell Size	3.280
Difference Mean	-0.006
Difference Median	-0.002
Difference Std. Dev	0.081
Difference Range	[-1.085, 1.210]
Mean + 2*Stddev	0.169
Median + 2*Stddev	0.165
Data Mean	-61.517
Reference Mean	-61.511
Data Z-Range	[-229.035, -12.179]
Reference Z-Range	[-229.258, -13.089]

Figure 2-6. Everett Landing South – IHO Special Order Compliance Test

Statistic	Value
Special Order Error Limit	0.466896
Special Order # Rejected	12090
Special Order P-Statistic	0.00715611
Special Order Test	ACCEPTED
Number Of Points	1689466
Grid Cell Size	3.280
Difference Mean	0.005
Difference Median	0.008
Difference Std. Dev	0.135
Difference Range	[-1.870, 2.176]
Mean + 2*Stddev	0.275
Median + 2*Stddev	0.278
Data Mean	-52.572
Reference Mean	-52.577
Data Z-Range	[-200.725, -5.173]
Reference Z-Range	[-199.590, -5.836]

Figure 2-7. Hat Island Landing – IHO Special Order Compliance Test

Statistic	Value
Order 1 Error Limit	5.74944
Order 1 # Rejected	1
Order 1 P-Statistic	8.38778e-06
Order 1 Test	ACCEPTED
Number Of Points	119221
Grid Cell Size	3.280
Difference Mean	-0.249
Difference Median	-0.241
Difference Std. Dev	0.352
Difference Range	[-2.074, 8.090]
Mean + 2*Stddev	0.954
Median + 2*Stddev	0.946
Data Mean	-440.838
Reference Mean	-440.589
Data Z-Range	[-450.277, -419.054]
Reference Z-Range	[-450.331, -419.181]

Figure 2-8. Cable Route Deep Water – IHO Order 1a Compliance Test

As a final comparison an area of overlap between this survey and MBE data previously collected by Tetra Tech, in 2017, off the Everett landing was examined. The two surveys showed excellent alignment with contours closely matching over most of the area, and some variations attributed to sediment movement identified around Pigeon Creek outflow. An example of the comparison with the new data on top and the border identified in dashed red is provided in Figure 2-9.




Figure 2-9. Data Comparison between Tetra Tech Data Recorded in this Survey, and an Overlapping Survey Area from 2017

3. DATA DELIVERABLES

The bathymetric survey data were incorporated into the project deliverables which include the following:

1. Bathymetry - ASCII format gridded bathymetry of the multibeam data service gridded to 1.5 x 1.5 ft, 3.0 x 3.0 ft and 4.5 x 4.5 ft sizes (delivered electronically)
2. Bathymetric contours at 5 and 10 ft elevation intervals, in shapefile (.shp) format (Attachment C, delivered electronically)

3. Charts showing the shaded relief bathymetry DEM surface with elevation contours and slope (included in Attachment D and delivered electronically as .pdf)
4. A brief survey report (this report) summarizing survey methods, data acquired, and the data deliverables.

4. DATA DISCUSSION

4.1 General Morphology

The general morphology along the route reflects the origins of Puget Sound as a glacially sculpted environment with steep, rocky slopes on the islands and mainland shoreline separated by relatively flat, sedimented seabed. The route runs between Hat Island to the south and the Port Gardner Bay embayment to the northeast. The Snohomish River system, the second largest river discharge into Puget Sound, empties into Port Gardner Bay at the City of Everett, north of the Primary and Alternate landings. Sediment waves are apparent along the western slope of the embayment and numerous turbidity flows cut the slope, bringing sediments across route corridor, particularly in the narrow channel between Hat Island and the embayment slope. Mobile sediments are also apparent on the western side of the route on the submerged portion of Hat Island that extends to the southeast. These mobile sediments are evident in regional bathymetry and in the bathymetric survey data along both sides of the survey corridor.

In the narrowest portion of the channel, mid-way between the landings, the seabed drops steeply to the maximum depth along the route of approximately 454 feet and the route crosses a turbidity flow where sediments have spread into a fan shape that abuts the eastern slope of Hat Island (Figure 4-1 and Figure 4-2).




Figure 4-1. Seabed descends steeply and route crosses the tow of a turbidity flow.




Figure 4-2. Cross-sectional profile through an area of side slopes

From the split between the Primary and Alternate routes to the landings at Everett the depths generally shoal gradually until they reach the base of the slope of the shoreline at a point about 2,500 feet from the cable termination. In the last 2,500 feet of the routes at the Everett landing the depths shoal rapidly from approximately 340 feet to the landfalls.

4.1.1 Hat Island Landing

The bathymetry at Hat Island has a moderate slope (5°-10°) from the shallow water limit of the survey to approximately 60 feet of water, then the seabed descends steeply to very steeply (15° to >20°) to the base of the slope at approximately 340 feet deep before essentially flattening out (slopes generally <1°) (Figure 4-3).




Figure 4-3. Hat Island Landing Bathymetry

4.1.2 Everett Primary Landing

The bathymetry towards the approach to the Primary landing shoals gently to approximately 310 feet of water. From approximately the 330-foot contour to the base of the slope numerous point features are scattered across the corridor. These objects, typically under 2 feet in height, are likely boulders or glacial erratics or other obstructions (Figure 4-4).




Figure 4-4. Approach to Everett Primary Landing

From approximately the 310-foot contour the seabed steepens moderately to steeply (5° to 20°) to the top of the slope and the shallow water limit of the survey vessel. The slope is generally smooth.

Approximately 300 feet south of the survey route is a submerged channel associated with Pigeon Creek. The Pigeon Creek channel feature has a depth of approximately 15 feet and comparisons with other data indicate potential sediment mobility in this area (Figure 4-5).

The approach to the Primary Landing area also includes a prominent seabed scar (potential anchor drag scar) detailed in Section 4.2.




Figure 4-5. Slope to Everett Primary Landing

4.1.3 Everett Alternative Landing

From the split off the Primary route the Alternate route crosses seabed that is relatively flat to gently sloping ($<5^\circ$) to the west and southwest. A few scattered point features as noted on the approach to the Primary Landing as likely glacial erratics (approximately 3 feet in height) were observed in approximately 350 feet of water. From a water depth of approximately 340 feet the seabed steepens quickly (5° - 20°) to the shallow water limit of the survey vessel at the Alternative Landing.

The Alternative Landing area includes two potential anthropogenic objects that area detailed in Section 4.2.

4.2 Features of Interest

Tetra Tech reviewed the bathymetry data for evidence of sea grasses, shipwrecks, debris or other features that may present a hazard to the proposed cable. Findings are presented in Sections 4.2.1 and 4.2.2.

4.2.1 Features and Potentially Anthropogenic Objects

Details on features observed in the bathymetry data are provided in Table 4-1.

Table 4-1. Features Observed in Bathymetric Data

	X	Y	Lat	Long	Z/Depth (ft)
Alternative Everett Landing Object 1	1293869	355853	47.96682316	-122.24802518	353.4
Primary Everett Landing Feature 1	1294104	359252	47.97615096	-122.24732298	314.2
Seabed Scars on Main Line (center point position)	1281664	373460	48.014459	-122.299203	330.4

The object detected at the Alternative Everett Landing is rectangular in shape and measures approximately 110 feet x 45 feet, with a height of approximately 5 feet. The top appears generally flat (Figure 4-6).




Figure 4-6. Alternate Everett Landing Object 1

At the approach to the Primary Everett Landing, numerous seabed scars were observed in the data at the base of a debris flow coming into the route corridor from the north; the largest scar is detailed in Figure 4-7. The stretch of the route is also located just over 385 feet from the southern corner of the main anchorage area for the Port of Everett (General Anchorage Area No. 110.230 on NOAA charts).

The largest and deepest scar is approximately 500 feet in length and 18 feet wide. These features are likely anchor drag scars.




Figure 4-7. Primary Everett Landing Seabed Scars

Additional seabed scars were detected approximately 1.3 miles from the Hat Island landing. Two scars form a 'Y' shaped depression oriented approximately N70°E. Another, less distinct scar oriented N3°W was detected approximately 2,000 feet to the east along the route. The first set of scars are 0.3 to 0.9 feet deep compared to the surrounding seabed, generally deepening toward its western extent, and are approximately 20-30 feet wide with no furrows (Figure 4-8).




Figure 4-8. Linear Seabed Scars Near Hat Island

4.2.2 Sea Grasses

The bathymetry data were assessed for the presence of sea grasses at each landing. These areas are shown in green on the charts provided in Appendix C. Small areas (approx. 600 x 10 feet) of possible sea grasses were identified at the Hat Island in the survey corridor but not along the planned cable route. At the Alternate Everett Landing, possible seagrasses were detected across the survey corridor, including on the planned cable route. Possible sea grass areas were only detected in water depths shallower than 25 feet, at the extreme shallow water limits of the bathymetry survey coverage.

Seagrasses were not detected in the Primary Everett Landing data.

APPENDIX A: ASCII FORMAT GRIDDED BATHYMETRY OF THE MULTIBEAM DATA

(DELIVERED ELECTRONICALLY)

APPENDIX B: SHP FILES OF CONTOURS AT 5 AND 10FT ELEVATION INTERVALS

(DELIVERED ELECTRONICALLY)

APPENDIX C: CHARTS SHOWING THE SURVEY CORRIDOR, HILLSHADE DEM SURFACE, ELEVATION CONTOURS AND SLOPE